LAYOUT PLAN 1

LAYOUT PLAN SHOWING PROP. RESI.+COMM. BLDG. ON S.P. – 1, SUR.NO. 11/3, O.P.NO. 84/3 OF F.P.NO. 84/3, OF DRAFT T.P.S.NO. 85 (SARKHEJ–MAKARBA –OKAF), AT.: SARKHEJ TA.: VEJALPUR, DIST.: AHMEDABAD.

ZONE : RESIDENCE–I SCALE : 1 CM.= 2.0 MT.

BLOCK–B

USE : RESI.+COMM.

AREA TABLE	SQ.MTS.
SUB PLOT–2 AREA	2250.82
REQ.COMMON PLOT 10%	225.08
COMMON PLOT PROVIDED	267.94
PROP. B.A.REA ON GROUND FLOOR	1008.08

F.S.I. AREA TABLE		F.S.I.
PLOT AREA		2250.82
PERMI. F.S.I. 1.8 OF PLOT AREA	(2250.82 X 1.80)	4051.48
PERMI. PYMT. F.S.I. 0.90 OF PLOT AREA	(2250.82 X 0.90)	2025.74
TOTAL PERMI. F.S.I. AREA		6077.22
PROP. F.S.I. ON BASEMENT		367.46
PROP. F.S.I. ON GROUND FLOOR(255.19)+SOC.OFFICE(31.28)		286.47
PROP. F.S.I. ON 1ST FLOOR		783.34
PROP. F.S.I. ON 2ND FLOOR		850.64
PROP. F.S.I. ON 3RD FLOOR		757.64
PROP. F.S.I. ON 4TH FLOOR		757.64
PROP. F.S.I. ON 5TH FLOOR		757.64
PROP. F.S.I. ON 6TH FLOOR		757.64
PROP. F.S.I. ON 7TH FLOOR		757.64
TOTAL PROP. F.S.I. AREA USED		6076.31
PAYMENT F.S.I. AREA USED	(6076.31 - 4051.48)	2024.83

COLOUR NOTES :

PLOT BOUNDARY, O.P. BOUNDARY, ROAD / RAMP, PROP. WORK, PROP. DRAINAGE, TREE, PERCOLATING WELL, COMMUNITY BINS

NOTES :

- ENGINEER IS FULLY RESPONSIBLE FOR LEAVING OPEN SPACE AND MARGIN.
- THE DEPTH AND POSITION OF EXISTING MUNICIPAL MANHOLE IS VERYFIED ME ON SITE AND PREMISISES GET CAN DRAINAGE CONNECTION.
- IT IS CERTIFY THAT ACCORDING TO GDCR 2021 ALL REQUIRMENTS OF THE BUILDING ARE CHECKED AND NECESSARY ACTIONS ARE TAKEN .
- IT IS CERTIFY THAT ACCORDING TO THE CLAUSE NO. 4.5.3 OF THE GDCR 2021, THE STRUCTURE OF THE BUILDING ISDESIGN AS PER THE NORMS OF THE INDIAN STANDARDS.
- DESIGN OF STAIRCASE AND RAILING IS PROVIDED AS PER THE PROVISION OF THE CLAUSE NO. 23.1.12 AND 23.14 AND 24.6 OF GDCR 2021
- PEDESTRIANS RAMP IS PROVIDED AS PER THE PROVISION OF THE CLAUSE NO. 23.1.5 OF GDCR 2021
- LIFT IS PROVIDED AS PER THE PROVISION OF THE CLAUSE NO. 23.12 AND 24.7 OF GDCR 2021
- WATER TANK IS PROVIDED AS PER THE PROVISION OF THE CLAUSE NO. 23.6 OF GDCR 2021
- SEPARATE LETTER BOX IS PROVIDED AT GROUND LEVEL FOR EACH UNIT.
- WATER TANK FOR FIRE SAFETY REQUIREMENT PROVIDED AS PER CHEPTER NO. 34 OF GDCR 2021
- ELECTRICAL INFRASTRUCTURE SHALL BE PROVIDED AS PER CLAUSE NO. 23.11
- DRAINAGE FACILITY IS PROVIDED AS PER THE CLAUSE NO. 23.10
- SIGNAGES OF THE PARKING PLACE IS TO BE PROVIDED AS PER THE CLAUSE NO. 23.7 OF THE GDCR 2021
- ENTRANCE OF THE BUILDING IS PROVIDED AS PER THE CLAUSE NO. 23.1.7 OF GDCR 2021
- THE PAVING OF BUILDING UNITPNL PLOT AS PER THE PROVISION OF THE CLAUSE NO. 23.1.4 OFGDCR 2021
- THE STRUCTUE OF THE BUILDING IS AS PER THE NORMS OF THE SPECIFIED IN THE INDIAN STANDARD AND TAKENACESSARY ACTION FOR THE STRUCTRAL SAFETY DURING THE CONSTRUCTION.
- RAIN WATER STORAGE TANK AND RAIN WATER HARVESTING SYSTEM IS PROVIDED AS PER THE CLAUSE NO. 27.2 OF GDCR 2021
- COMMUNITY BIN PROVIDED AS PER THE PROVISION OF THE CLAUSE NO. 37.3 OF GDCR 2021
- TREE PALNTATION IS PROVIDED AS PER THE CLAUSE NO. 27.5 OF GDCR 2021
- MAINTANANCE AND UPGRADATION OF BUILDING IS AS PER CHAPETER NO. 29 OF GDCR 2021
- EXTERNAL FACED AREA PROVIDED 50% AS PER GDCR 2021
- GREY WATER RECYCLING SYSTEM IS PROVIDED AS PER THE CLAUSE NO. 27.4 OF GDCR 2021
- SOLAR WATER HEATING SYSTEM IS PROVIDED AS PER THE CLAUSE NO. 27.6 OF THE GDCR 2021
- POLLUTION CONTROL SYSTEM IS PROVIDED AS PER THE CHAPTER NO. 28 OF GDCR 2021
- FIRE SAFETY SYSTEM IS PROVIDED AS PER CHAPETER NO. 24 OF GDCR 2021
- GARBAGE SHAFT SHALL BE PROVIDED AS PER INDIAN STANDARD SPECIFICATION.
- DUAL PLUMBING SYSTEM SHALL BE PROVIDED AS PER INDIAN STANDARD SPECIFICATION.

SANITARY PROVISION TABLE

TOTAL FLOOR AREA = 1190.01 SQ.MTS

1 USER PER 4.00 SQ.MTS. PER CARPET AREA=

1190.01 / 4.00 SQ.MTS. = 297.50 SAY - 298 USERS

REQ.	W.C.	URINAL
UP TO 20 PERSON	1	1
21 - 100 PERSON	4	4
101-500 PERSON	4	4
TOTAL REQ.	9	9

PROVIDED 23 TOILET IN SHOPS

SANITARY PROVISION TABLE (COMMON)

REQ. 25% COMMON SANITARY FOR GENRAL

URINAL = 9 X 0.25 = 3 USERS

W/C = 9 X 0.25 = 3 USERS

FOR EACH GENDER

1 TOILET FOR HANDICAP PERSON

PROVIDED 3 TOILET & 1 HANDICAP PERSON TOILET

AVIS BUILDCON
Dev. Lic. No. 766180721
Devnandan Mega Mall,
Nr. M. J. Library, Ashram Road,
Ellisbridge, AHMEDABAD-380 006.

DEVELOPER

For, M/s. Avis Buildcon
Partner

OWNER

Pitamber N. Sitlani
BE (CIVIL)
Licence No.: CW-05708720
G-329, Safal-6, BRTS Road,
Dudheshwar, Ahmedabad.
Mobile: 7574864480

C.O.W.

A. Y. CHHIPA
B.E. (CIVIL)M. I. E.
STRUCTURAL DESIGNER GRADE-I
AMC LIC NO. SB 86/01/01/0721R3

ST. ENGINEER

M. K. NOORANI (ARCHITECT)
LIC - AR 0162020617
5-11, APMC Market,
Nr. Vishala Circle, Vasna,
Ahmedabad-55. Ph.: 2662 5333

ENGINEER

Ahmedabad Municipal Corporation
Case No. : BLNTSNWZ/0510/1GDR/A7331/R0/M1 Zone: New West
Plan Approved as per terms and condition mentioned in the Commencement Certificate.
Raja Chithi Number : 7704/0310/AA7331/R0/M1
Date : 03/02/2017

Dy Executive Engineer (Civic Center) | Asst. T.D.O.(Asst. E.O. (Civic Center) | CHAITANYA J. SHAH (IC) Dy T.D.O. New West | C.R. VORPEN (IC) Dy Mc. New West

AUTHORITY

SCRUTINIZE COPY
No. 3520 Dt. 04/2/17
TDO, BPSP, AMC



ELE. SUB STATION AREA CALC.

GROUND FLOOR
4.11 X 4.48 = 18.41 SQ.MTS.
1.00 X 4.48 = 4.48 SQ.MTS.
TOTAL = 22.89 SQ.MTS.
FIRST FLOOR
4.11 X 4.48 = 18.41 SQ.MTS.
GR.+1ST FL. (22.89+18.41) =41.30 SM.

SOCIETY OFFICE AREA CALC.

8.00 X 3.91 = 31.28 SQ.MTS.

BUILT UP AREA IN COMMON PLOT	
COMMON PLOT AREA	267.94 SQ.MTS.
PERMI. GR.FL. @ 15%	40.19 SQ.MTS.
PROV. BUILT AREA IN C.P.	31.28 SQ.MTS.
BALANCE B.UP AREA	8.91 SQ.MTS.

BUILT–UP AREA TABLE

	BLOCK-A	BLOCK-B	SOC.ARE SUB	TOTAL
BASEMENT	1479.36	-----	-----	1479.36
GROUND FLOOR	518.76	435.15	31.28+22.89=54.17	1008.08
1ST FLOOR	518.76	435.15	18.41	972.32
2ND FLOOR	518.76	435.15	-----	953.91
3RD FLOOR	404.85	435.15	-----	840.00
4TH FLOOR	404.85	435.15	-----	840.00
5TH FLOOR	404.85	435.15	-----	840.00
6TH FLOOR	404.85	435.15	-----	840.00
7TH FLOOR	404.85	435.15	-----	840.00
STAIR CABIN	37.77	41.38	-----	79.15
LIFT MC. ROOM & D.H.W.T.	20.34	22.04	-----	47.38
TOTAL	5123.00	3544.62	72.58	8740.20

F.S.I. AREA TABLE

	BLOCK-A	BLOCK-B	SOC.OFFICE	TOTAL
BASEMENT	367.46	-----	-----	367.46
GROUND FLOOR	255.19	-----	31.28	286.47
1ST FLOOR	386.24	397.10	-----	783.34
2ND FLOOR	453.74	397.10	-----	850.84
3RD FLOOR	360.54	397.10	-----	757.64
4TH FLOOR	360.54	397.10	-----	757.64
5TH FLOOR	360.54	397.10	-----	757.64
6TH FLOOR	360.54	397.10	-----	757.64
7TH FLOOR	360.54	397.10	-----	757.64
TOTAL	3265.33	2779.70	31.28	6076.31

USE,UNITS & FLOOR AREA TABLE

	USE	UNIT A	UNIT B	TOTAL	FLOOR AREA BLOCK-A	FLOOR AREA BLOCK-B	TOTAL
BASEMENT	STORE+PARKING	---	---	---	1419.70	-----	1419.70
GROUND FLOOR	SHOP+RMBO+SOC.+LOBBY	11+2+11	---	11+0+11	253.75	-----	253.75
1ST FLOOR	SHOP+RESI.+OLE SUB	10+2+12	4	10+0+16	399.72	397.10	796.82
2ND FLOOR	OFFICE+RESI.	6+2+8	4	6+0+12	454.91	397.10	852.01
3RD FLOOR	RESI.	5	4	9	360.54	397.10	757.64
4TH FLOOR	RESI.	5	4	9	360.54	397.10	757.64
5TH FLOOR	RESI.	5	4	9	360.54	397.10	757.64
6TH FLOOR	RESI.	5	4	9	360.54	397.10	757.64
7TH FLOOR	RESI.	5	4	9	360.54	397.10	757.64
TOTAL		27+3=30	20	27+47=94	3175.76	2779.70	6095.46