

AHMEDABAD MUNICIPAL CORPORATION
FIRE & EMERGENCY SERVICE
DANAPITH FIRE STATION, (H. Q.)AHMEDABAD - 380 001
PH. : (079) 22148466 / 67 / 68, 32981178, 32981500 FAX : (079)

No. - OPN469711072022 Dt.:11/07/2022

To,

NEST INFINITY,

NEST INFINITY NIKOL AHMEDABAD

NEST INFINITY NIKOL AHMEDABAD

Sub: Fire safety & protection, opinion for a proposed high-rise building / Low-Rise Building - High Rise Building

Sir,

This is to intimate that , the plans submitted for, High Rise Building , have all the required line drawings and write-up are as per the requirement of fire prevention and protection.

ALL NORMS AS PER THE NBC-2016 PART-IV FIRE AND LIFE SAFETY GUIDELINES / GUJARAT STATE MEASURES ACT - RULES / GDCR (2021) & CBD BY AUDA / SPECIAL INSTRUCTIONS GIVEN BY FIRE OFFICER HAVE TO BE FOLLOWED AS FAR AS THE CONSTRUCTION AND FIRE PREVENTION FOLLOWED AS BELOW.

Staircase :

1.5 meters for 9 to 25 meters building heights.

2.00 meters for 25 meters to above building heights, clear in width.

It is required that all staircases of the building shall be ventilated above the parapet wall at each floor level and shall be 2 meters clear in width.

The staircase and lift shafts shall not go to the basement but if they go they have to be protected by 2 hours fire resistant construction including the doors.

All fire doors of the building shall be certified for stability, integrity & insulation by fire research laboratory, institute, roorkee-247-667.

A motorable road with 45 ton load bearing capacity and minimum as metion in table; is required around the building without obstruction to a clear motorable passage for fire/rescue vehicles.

Any transformer to be installed shall be away from the building & leaving open Space required around the building and below building height wise open space required around the building.

Margin for different types of building;

1) 15 to 25 Meters building - 3 meters

Plot area more than 750 sq. mt. : 4 Meters

2) Up to 45 Meters building : 6 Meters

3) Up to 70 Meters building : 8 Meters

The gate (entry) to the premises shall be minimum 6 meters or more if required, in width, entry gate to be provided on both sides.

The Fire Protection system shall be as mentioned in the approved plans.

1. All basements parking and HPP shall be fully sprinklered.
2. All lower basements should have positive pressure ventilation.
3. Electric Cable Shaft should have fire resistant doors.

In this Filed we can write what system they required in building – So whatever here we write that can be mention in final opinion letters

Name of Building		NEST INFINITY		
Site Address		NEST INFINITY NIKOL AHMEDABAD		
T.P.No.		119 (NIKOL)		
F.P.No.		21		
R.S.No.		100		
Sub Plot No.		-		
Surrounding Margin from building				
Common Plot Margin from building				
Building Type		High Rise Building		
		BLOCK :- A+B		BLOCK :- C+D
Fire Opinion Remarks	ALL BASEMENT PARKING, HPP & SHOPS AT ALL LEVEL SHALL BE FULLY SPRINKLERED. •ALL BASEMENTS SHOULD HAVE POSITIVE PRESSURE VENTILATION SYSTEM / NATURAL VENTILATION SYSTEM WITH REQUIRED DUCT. •ELECTRIC CABLE DUCT SHOULD HAVE FIRE RATED DOORS AT ALL LEVEL AND TO BE KEPT OPEN FROM TERRACE AND GROUND / LAST BASEMENT LEVEL. •STAIRCASE AND LIFT LOBBY TO BE ENCLOSED AT BASEMENT. HYDRANT SYSTEM (CONVENTIONAL) ONLY CLASS-C PIPES TO BE USED FIRE PUMP NOT TO BE INSTALLED LOWER THAN 2ND BASEMENT. - FIRE PUMP CAPACITY TO DISCHARGE 900 LITERS PER MINUTE @ 3 BAR PRESSURE MEASURED AT TERRACE LEVEL. - ONE HYDRANT VALVE AND ONE HOSE REEL HOSE WITH ON / OFF SWITCH FOR THE FIRE PUMP (ONE SET PER FLOOR AREA OF 1000 SQ. METERS.) - RISER CUM DOWN COMMER TO BE PROVIDED 100 MM. DIAMETER UP TO 30 METERS, 150 MM. FOR BUILDINGS ABOVE 30 METERS. - ONE UNIT OF CO2 EXTINGUISHER 4.5 KGS AND ONE UNIT OF DCP EXTINGUISHER OF 6 KGS. PER FLOOR (ONE SET PER 1000 SQ. METERS) - FIRE SERVICE INLET TO BE PROVIDED AT THE GROUND LEVEL. • STAND ALONE WITH INBUILT BATTERY TYPE OF SMOKE/ HEAT DETECTORS ARE NOT PERMITTED IN ANY KIND OF OCCUPANCY.		SAME AS BLOCK - A	
Block Height From Ground Level to Top Slab(In Meter)	44.1		44.1	
	Use	Height(In Meter)	Use	Height(In Meter)
Basement 2	PARKING	3.8000	PARKING	3.8000
Basement 1	PARKING	3.6600	PARKING	3.6600

Hollow Plinth/Ground Floor	SHOP + PARKING + ELE SUB-STATION	3.5000	PARKING	3.5000
Floor 1	RESIDENCE + SHOP	2.9000	RESIDENCE	2.9000
Floor 2	RESIDENCE	2.9000	RESIDENCE	2.9000
Floor 3	RESIDENCE	2.9000	RESIDENCE	2.9000
Floor 4	RESIDENCE	2.9000	RESIDENCE	2.9000
Floor 5	RESIDENCE	2.9000	RESIDENCE	2.9000
Floor 6	RESIDENCE	2.9000	RESIDENCE	2.9000
Floor 7	RESIDENCE	2.9000	RESIDENCE	2.9000
Floor 8	RESIDENCE	2.9000	RESIDENCE	2.9000
Floor 9	RESIDENCE	2.9000	RESIDENCE	2.9000
Floor 10	RESIDENCE	2.9000	RESIDENCE	2.9000
Floor 11	RESIDENCE	2.9000	RESIDENCE	2.9000
Floor 12	RESIDENCE	2.9000	RESIDENCE	2.9000
Floor 13	RESIDENCE	2.9000	RESIDENCE	2.9000
Floor 14	RESIDENCE	2.9000	RESIDENCE	2.9000

Ramp only permitted for 15 to 25 meters building in margin.

Basic Fire Requirement Notes on plan

After, the building is built and all the required Fire safety and Protection equipment have been installed and after due inspection by the Fire service officer an NOC can be issued.

Note : if plans are submitted for only industrial building approval, Industrial Building -

Information about all processes, raw material and finished material shall be mentioned in plan.

(JAYESH N. KHADIA)



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

AHME/WEST/B/071721/561912

मालिक का नाम एवं पता

Sureshbhai Parshottambhai

दिनांक/DATE:

09-08-2021

OWNERS Name &
Address

F.P.No. 21, Opp. Rajvi
Residency, Bhojaldham Road, Nikol,
Ahmedabad.

वैधता/ Valid Up to:

08-08-2029

ऊँचाई की अनुमति हेतु अनापत्ति प्रमाण पत्र (एनओसी) No Objection Certificate for Height Clearance

1) यह अनापत्ति प्रमाण पत्र भारतीय विमानपत्तन प्राधिकरण (भाविप्रा) द्वारा प्रदत्त दायित्वों के अनुक्रम तथा सुरक्षित एवं नियमित विमान प्रचालन हेतु भारत सरकार (नागर विमानन मंत्रालय) की अधिसूचना जी. एस. आर. 751 (ई) दिनांक 30 सितम्बर, 2015, जी. एस. आर. 770 (ई) दिनांक 17 दिसंबर 2020 द्वारा संशोधित, के प्रावधानों के अंतर्गत दिया जाता है।
1. This NOC is issued by Airports Authority of India (AAI) in pursuance of responsibility conferred by and as per the provisions of Govt. of India (Ministry of Civil Aviation) order GSR751 (E) dated 30th Sep.2015 amended by GSR770(E) dated 17th Dec 2020 for safe and Regular Aircraft Operations.

2) इस कार्यालय को निम्नलिखित विवरण के अनुसार प्रस्तावित संरचना के निर्माण पर कोई आपत्ति नहीं है।

2. This office has no objection to the construction of the proposed structure as per the following details:

अनापत्ति प्रमाणपत्र आईडी / NOC ID	AHME/WEST/B/071721/561912
आवेदक का नाम / Applicant Name*	Bhargav Savaliya (Mo. No. 9998982893)
स्थल का पता / Site Address*	Sur. No. 100, F.P.No. 21, T.P.S. No. 119 (Nikol), At. Nikol, Ta. Asarwa, Dist. Ahmedabad., Nikol, Ahmedabad, Gujarat
स्थल के निर्देशांक / Site Coordinates*	23 02 02.43N 72 40 12.56E, 23 02 05.11N 72 40 12.81E, 23 02 02.24N 72 40 14.24E, 23 02 04.95N 72 40 14.47E
स्थल की ऊँचाई एएमएसएल मीटर में (औसतन समुद्र तल से ऊपर), (जैसा आवेदक द्वारा उपलब्ध कराया गया) / Site Elevation in mtrs AMSL as submitted by Applicant*	54.33 M
अनुमत्य अधिकतम ऊँचाई एएमएसएल मीटर में (औसतन समुद्र तल से ऊपर) / Permissible Top Elevation in mtrs Above Mean Sea Level(AMSL)	109.33 M

* जैसा आवेदक द्वारा उपलब्ध कराया गया / As provided by applicant*



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

AHME/WEST/B/071721/561912

3) यह अनापत्ति प्रमाण पत्र निम्नलिखित नियम व शर्तों के अधीन है: -

3. This NOC is subject to the terms and conditions as given below:

क) आवेदक द्वारा उपलब्ध कराए गए स्थल की ऊँचाई तथा निर्देशांक को, प्रस्तावित संरचना हेतु अनुमन्य अधिकतम ऊँचाई जारी करने के लिए प्रयोग किया गया है। भारतीय विमान पत्तन प्राधिकरण, आवेदक द्वारा उपलब्ध कराये गए स्थल की ऊँचाई तथा निर्देशांक की यथार्थता का ना तो उत्तरदायित्व वहन करता है, और ना ही इनको प्रमाणीकृत करता है। यदि किसी भी स्तर पर यह पता चलता है कि वास्तविक विवरण, आवेदक द्वारा उपलब्ध कराए गए विवरण से भिन्न है, तो यह अनापत्ति प्रमाण पत्र अमान्य माना जाएगा तथा कानूनी कार्यवाही की जाएगी। सम्बंधित विमान क्षेत्र के प्रभारी अधिकारी द्वारा एयरक्राफ्ट नियम 1994 (भवन, वृक्षों आदि के कारण अवरोध का विध्वंस) के अधीन कार्यवाही की जायेगी।

a. Permissible Top elevation has been issued on the basis of Site coordinates and Site Elevation submitted by Applicant. AAI neither owns the responsibility nor authenticates the correctness of the site coordinates & site elevation provided by the applicant. If at any stage it is established that the actual data is different, this NOC will stand null and void and action will be taken as per law. The officer in-charge of the concerned aerodrome may initiate action under the Aircraft (Demolition of Obstruction caused by Buildings and Trees etc.) Rules, 1994",

ख) अनापत्ति प्रमाण पत्र के आवेदन में आवेदक द्वारा उपलब्ध कराए गए स्थल निर्देशांक को सड़क दृश्य मानचित्र और उपग्रह मानचित्र पर अंकित किया गया है जैसा कि अनुलग्नक में दिखाया गया है। आवेदक / मालिक यह सुनिश्चित करे कि अंकित किए गए निर्देशांक उसके स्थल से मेल खाते हैं। किसी भी विसंगति के मामले में, नामित अधिकारी को अनापत्ति प्रमाण पत्र रद्द करने के लिए अनुरोध किया जाएगा।

b. The Site coordinates as provided by the applicant in the NOC application has been plotted on the street view map and satellite map as shown in ANNEXURE. Applicant/Owner to ensure that the plotted coordinates corresponds to his/her site. In case of any discrepancy, Designated Officer shall be requested for cancellation of the NOC.

ग) एयरपोर्ट संचालक या उनके नामित प्रतिनिधि, अनापत्ति प्रमाण पत्र नियमों और शर्तों का अनुपालन सुनिश्चित करने के लिए स्थल (आवेदक या मालिक के साथ पूर्व समन्वय के साथ) का दौरा कर सकते हैं।

c. Airport Operator or his designated representative may visit the site (with prior coordination with applicant or owner) to ensure that NOC terms & conditions are complied with.

घ) संरचना की ऊँचाई (सुपर स्ट्रक्चर सहित) की गणना अनुमन्य अधिकतम ऊँचाई (ए एम एस एल) से स्थल की ऊँचाई को घटाकर की जायेगी। अर्थात्, संरचना की अधिकतम ऊँचाई = अनुमन्य अधिकतम ऊँचाई (-) स्थल की ऊँचाई।

d. The Structure height (including any superstructure) shall be calculated by subtracting the Site elevation in AMSL from the Permissible Top Elevation in AMSL i.e. Maximum Structure Height = Permissible Top Elevation minus (-) Site Elevation.

च) अनापत्ति प्रमाण पत्र जारी करना, भारतीय एयरक्राफ्ट एक्ट 1934, के सैक्शन 9-A तथा इसके अंतर्गत समय-समय पर जारी अधिसूचनाएं तथा एयरक्राफ्ट नियम (1994 भवन, वृक्षों आदि के कारण अवरोध का विध्वंस) के अधीन है।

e. The issue of the 'NOC' is further subject to the provisions of Section 9-A of the Indian Aircraft Act, 1934 and any notifications issued there under from time to time including, "The Aircraft (Demolition of Obstruction caused by Buildings and Trees etc.) Rules, 1994".



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

AHME/WEST/B/071721/561912

छ) कोई भी रेडियो/ टीवी एन्टीना, लाइटनिंग अरेस्टर, सीढ़िया, मुमटी, पानी की टंकी अथवा कोई अन्य वस्तु तथा किसी भी प्रकार के संलग्नक उपस्कर पैरा 2 में उल्लेखित अनुमन्य अधिकतम ऊँचाई से ऊपर नहीं जानी चाहिए।

f. No radio/TV Antenna, lightening arresters, staircase, Mumty, Overhead water tank or any other object and attachments of fixtures of any kind shall project above the Permissible Top Elevation as indicated in para 2.

ज) विमानक्षेत्र संदर्भ बिंदु के 8 KM के भीतर तेल, बिजली या किसी अन्य ईंधन का उपयोग जो उड़ान संचालन के लिए धुएँ का खतरा पैदा नहीं करता है, ही मान्य है।

g. Use of oil, electric or any other fuel which does not create smoke hazard for flight operation is obligatory, within 8 KM of the Aerodrome Reference Point

झ) यह प्रमाणपत्र इसके जारी होने की तारीख से 8 साल की अवधि के लिए वैध है। एक बार रिवेलीडेशन की अनुमति दी जा सकती है, बशर्ते कि इस तरह का अनुरोध एनओसी की समाप्ति की तारीख से छह महीने के भीतर किया जाए और प्रारंभिक प्रमाणपत्र 8 साल की वैधता अवधि के भीतर प्राप्त किया जाए।

h. The certificate is valid for a period of 8 years from the date of its issue. One-time revalidation shall be allowed, provided that such request shall be made within six months from the date of expiry of the NOC and commencement certificate is obtained within initial validity period of 8 years.

ट) भवन के निर्माण के दौरान या उसके बाद किसी भी समय स्थल पर ऐसी कोई भी लाइट या लाइटो का संयोजन नहीं लगाया जाएगा जिसकी तीव्रता, आकृति या रंग के कारण वैमानिक ग्राउन्ड लाइटों के साथ भ्रम उत्पन्न हो। विमान के सुरक्षित प्रचालन को प्रभावित करने वाली कोई भी गतिविधि मान्य नहीं होगी।

i. No light or a combination of lights which by reason of its intensity, configuration or colour may cause confusion with the aeronautical ground lights of the Airport shall be installed at the site at any time, during or after the construction of the building. No activity shall be allowed which may affect the safe operations of flights.

ठ) आवेदक द्वारा विमानपत्तन पर या उसके आसपास विमान से उत्पन्न शोर, कंपन या विमान प्रचालन से हुई किसी भी क्षति के विरुद्ध कोई शिकायत/दावा नहीं किया जाएगा।

j. The applicant will not complain/claim compensation against aircraft noise, vibrations, damages etc. caused by aircraft operations at or in the vicinity of the airport.

ड) डे मार्किंग तथा सहायक विद्युत आपूर्ति सहित नाइट लाइटिंग (डीजीसीए भारत की वेबसाइट www.dgca.nic.in पर उपलब्ध) नागर विमानन आवश्यकताएं श्रृंखला 'बी' पार्ट I सैक्शन-4 के चैप्टर 6 तथा अनुलग्नक 6 में विनिर्दिष्ट दिशानिर्देशों के अनुसार उपलब्ध कराई जाएंगी।

k. Day markings & night lighting with secondary power supply shall be provided as per the guidelines specified in chapter 6 and appendix 6 of Civil Aviation Requirement Series 'B' Part I Section 4, available on DGCA India website: www.dgca.nic.in

ढ) भवन के नक्शे के अनुमोदन सहित अन्य सभी वैधानिक अनापत्ति, संबंधित प्राधिकरणों से लेना आवेदक की जिम्मेदारी होगी, क्योंकि इस ऊँचाई हेतु अनापत्ति प्रमाणपत्र लेने का उद्देश्य सुरक्षित एवं नियमित विमान प्रचालन सुनिश्चित करना है तथा इसे भूमि के स्वामित्व आदि सहित किसी अन्य उद्देश्य/ दावे के लिए दस्तावेज के रूप में प्रयोग नहीं किया जा सकता।

l. The applicant is responsible to obtain all other statutory clearances from the concerned authorities including



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

AHME/WEST/B/071721/561912

the approval of building plans. This NOC for height clearances is only to ensure safe and regular aircraft operations and shall not be used as document for any other purpose/claim whatsoever, including ownership of land etc.

ण) इस अनापत्ति प्रमाणपत्र आईडी का मूल्यांकन Ahmedabad विमानक्षेत्रों के संबंध में किया गया है। यह अनापत्ति प्रमाणपत्र भारतीय विमान पत्तन प्राधिकरण के विमानक्षेत्रों और अन्य लाइसेंस प्राप्त सिविल विमानक्षेत्रों, जो जी. एस. आर. 751 (ई) जी. एस. आर. 770 (ई) द्वारा संशोधित के अनुसूची - III, अनुसूची - IV (भाग- I), अनुसूची- IV (भाग -2; केवल RCS हवाई अड्डे) और अनुसूची- VII में सूचीबद्ध हैं, के लिए जारी किया गया है।

m. This NOC ID has been assessed with respect to the Ahmedabad Airports. NOC has been issued w.r.t. the AAI Aerodromes and other licensed Civil Aerodromes as listed in Schedule – III, Schedule – IV(Part-I), Schedule- IV (Part-2; RCS Airports Only) and Schedule-VII of GSR 751(E) amended by GSR770(E)

त) यदि स्थल रक्षा विभाग के विमान क्षेत्र के अधिकार क्षेत्र में आता है, जैसा कि जीएसआर 751 (ई) की अनुसूची-V में सूचीबद्ध है, तो आवेदक को रक्षा विभाग से अलग से अनापत्ति प्रमाणपत्र लेना होता है। जीएसआर 751 (ई) जी. एस. आर. 770 (ई) द्वारा संशोधित के नियम 13 के अनुसार, आवेदकों को उन स्थलों के लिये, जो जीएसआर 751 (ई) जी. एस. आर. 770 (ई) द्वारा संशोधित के अनुसूची- IV (भाग -2; आरसीएस हवाई अड्डों के अलावा) के रूप में सूचीबद्ध बिना लाइसेंस वाले विमान क्षेत्र के अधिकार क्षेत्र में आता हैं, तो संबंधित राज्य सरकार से भी अनापत्ति प्रमाणपत्र लेने की आवश्यकता है।

n. Applicant needs to seek separate NOC from Defence, if the site lies within the jurisdiction of Defence Aerodromes as listed in Schedule – V of GSR 751 E amended by GSR770(E). As per rule 13 of GSR 751 E amended by GSR770(E), applicants also need to seek NOC from the concerned state government for sites which lies in the jurisdiction of unlicensed aerodromes as listed in Schedule-IV (Part-2; other than RCS airports) of GSR 751 E amended by GSR770(E)

थ) अनापत्ति प्रमाण पत्र (एनओसी) की किसी भी त्रुटि/व्याख्या की स्थिति में अंगरेजी अनुवाद ही मान्य होगा।

o. In case of any discrepancy/interpretation of NOC letter, English version shall be valid.

द) स्थल की ऊँचाई और/या संरचना की ऊँचाई के किसी भी विवाद में अनुमन्य अधिकतम ऊँचाई एएमएसएल में ही मान्य होगी।

p. In case of any dispute with respect to site elevation and/or AGL height, Permissible Top Elevation in AMSL shall prevail.



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

AHME/WEST/B/071721/561912

क्षेत्र का नाम / Region Name: पश्चिम/WEST

पदनामित अधिकारी/Designated Officer नाम/ पदनाम/दिनांक सहित हस्ताक्षर Name/Designation/Sign with date	 Digitally signed by TAPAN K NAYAK Reason: Asst. General Manager(ATM), Signed on behalf of DO NOCC Location: AAI, SVPI Airport, Ahmedabad-380003 Date: 2021-08-09 17:46+05:30
द्वारा तैयार Prepared by	
द्वारा जांचा गया Verified by	

ईमेल आईडी / EMAIL ID : vaah.noc@aai.aero
फोन/ Ph: 079-22858111

ANNEXURE/अनुलग्नक

Distance From Nearest Airport And Bearing/निकटतम विमानक्षेत्र से दूरी और बीयरिंग

Airport Name/ विमानक्षेत्र का नाम	Distance (Meters) from Nearest ARP/निकटतम विमानक्षेत्र संदर्भ बिंदु से दूरी (मीटर मे)	Bearing(Degree) from Nearest ARP/निकटतम विमानक्षेत्र संदर्भ बिंदु से बीयरिंग (डिग्री)
Ahmedabad	6037.06	132.88
NOCID	AHME/WEST/B/071721/561912	



**Government of India
Ministry of Environment, Forest and Climate Change
(Issued by the State Environment Impact Assessment
Authority(SEIAA), Gujarat)**

To,

The Partner

NEST INFINITY

Survey no 100, FP no 21, TPS no 119, At Nikol, Ta. Asarva, Dist.
Ahmedabad -382350

Subject: Grant of Environmental Clearance (EC) to the proposed Project Activity
under the provision of EIA Notification 2006-regarding

Sir/Madam,

This is in reference to your application for Environmental Clearance (EC)
in respect of project submitted to the SEIAA vide proposal number
SIA/GJ/MIS/284547/2022 dated 20 Jul 2022. The particulars of the environmental
clearance granted to the project are as below.

1. EC Identification No.	EC22B038GJ162229
2. File No.	SIA/GJ/133407/2022
3. Project Type	Expansion
4. Category	B2
5. Project/Activity including Schedule No.	8(a) Building and Construction projects
6. Name of Project	Nest Infinity
7. Name of Company/Organization	NEST INFINITY
8. Location of Project	Gujarat
9. TOR Date	N/A

The project details along with terms and conditions are appended herewith from page
no 2 onwards.

Date: 12/11/2022

(e-signed)
Prakash K. Majmudar
Member Secretary
SEIAA - (Gujarat)

*Note: A valid environmental clearance shall be one that has EC identification
number & E-Sign generated from PARIVESH. Please quote identification
number in all future correspondence.*

This is a computer generated cover page.

PARIVESH

*(Pro-Active and Responsive Facilitation by Interactive,
and Virtuous Environmental Single-Window Hub)*





No. SEIAA/GUJ/EC/8(a)/2669/2022

Date: 11 NOV 2022 BY R.P.A.D
Time Limit

Sub: Environment Clearance for the Building and Construction Project "Nest Infinity" at Survey No. 100, F.P. No. 21, T.P.S No. 119, At Nikol, Taluka Asarva, District: Ahmedabad Proposed by M/s. Nest Infinity. Construction project in Category 8 (a) of Schedule annexed with EIA Notification dated 14/09/2006.

Ref: Your Proposal No. SIA/GJ/MIS/284547/2022.

Dear Sir,

This has reference to your application along with Form-I, Form-1 A dated 20/07/2022, seeking Environmental Clearance under Environment Impact Assessment Notification, 2006. The project was scheduled for hearing in the SEAC meeting held on 01/09/2022.

The proposal is for Environmental Clearance for the Building and Construction Project "Nest Infinity" at Survey No. 100, F.P. No. 21, T.P.S No. 119, At Nikol, Taluka Asarva, District: Ahmedabad Proposed by M/s. Nest Infinity. This is a proposed building construction project having plot area of 3,581.00 m² and the proposed FSI area of the project is 16,052.77 m² with proposed built up area of 27,713.09 m². As the built up area is >20,000 m² and <1,50,000 m², it falls in the category 8(a) of the Schedule of EIA Notification, 2006.

The project will comprise of 02 numbers of buildings. No. of Blocks: 04. Scope of buildings/blocks are: Basement (1 & 2)+ Ground Floor / HP / SP + 14 Floor and No. & size of Residential Units are: 220 flats and No. & size of Commercial Units are: 18.

The project activity is covered in 8(a) and falls in Category 'B'. Since the proposed project is in item no.8 of the EIA notification, 2006, it does not need Public Consultation as per Para 7(i) III. Stage (3) (d) – Public Consultation of EIA Notification, 2006.

The SEAC, Gujarat had recommended the project vide their letter dated 04/10/2022 to grant Environmental Clearance to the SEIAA, Gujarat based on the decision taken during SEAC meeting held on 01/09/2022. The proposal was considered by SEIAA, Gujarat in its meeting held on 05/11/2022 at Gandhinagar. After careful consideration, the SEIAA hereby accords Environmental Clearance to above project under the provisions of EIA Notification dated 14th September, 2006 subject to the compliance of the following conditions.

A. PROJECT SPECIFIC CONDITIONS:

1. The treated wastewater discharge into AMC drainage line shall not exceed 65.1 KLD. Necessary permission from AMC shall be obtained for discharging of same in the drainage line. The treated water to be discharge should meet all standard limits prescribed as per the norms of GPCB/CPCB and competent authority shall display and inform to local bodies.
2. PP shall submit the occupational Health details within 15 days.
3. This Environmental Clearance supersedes the Environmental Clearance granted vide No. SEIAA/ GUJ/ EC/ 8(a)/1161/2022 dated 10/05/2022 and the same shall be treated as null & void.
4. Project Proponent shall submit CER plan to respective Collectors, DDO and Municipal Commissioner/Urban Development Authority and implement of CER activities under intimation and guidance of the respective authorities.

PP shall take all necessary steps for fire and life safety measures for fall protection, ladders and stairs, scaffolds, trenching and excavation, electrical safety, cranes, occupational noise exposure, welding and cutting etc.

The total parking area approved in EC should be earmarked with number of flats and allotment must be handed over to the maintenance of society when transferred with necessary notarized undertaking abide by all conditions of EC including disposal of waste, ventilation, lighting in basement area adequately.



A.1 CONSTRUCTION PHASE:

A.1.1 WATER:

7. Fresh water requirement during the construction phase shall not exceed 12.25 KLD and it shall be met through AMC/ Local Tanker No ground water shall be tapped during the construction phase.
8. Sewage generated during the construction phase shall be disposed off through Soak Pit.
9. Explore possibilities of provision of mobile toilets in construction phase.

A.1.2 HEALTH & SAFETY:

10. Project Proponent shall obtain Fire opinion/provisional fire NOC from the concern authority as per the prevailing Rules / Gujarat Fire Prevention and Life Safety Measures Act, 2016.
11. The project proponent shall obtain registration of the establishment under the Building and other Construction Workers' (Regulation of Employment & Conditions of Service) Act 1996 and shall comply with the provisions of the Act for the safety, health and welfare of construction workers.
12. The project proponent shall obtain registration of the construction workers as beneficiaries with the Gujarat Building and Other Construction Workers Welfare Board.

A.2 OPERATION PHASE:

A.2.1 WATER

13. Total water requirement during the operation phase shall not exceed 157.3 KLD, out of which fresh water requirement of 102.2 KLD shall be met through AMC and the remaining 55.1 KLD of water requirement shall be met through treated sewage. No ground water shall be tapped during the operation phase. Metering of the water shall be done and its records shall be maintained.
14. Sewage generation during operation phase shall not exceed 120.2 KLD which shall be treated in the proposed onsite Sewage Treatment Plant.
15. The unit shall install and efficiently operate STP of adequate capacity for treating the sewage to be generated during operation phase to achieve the GPCB norms at the STP outlet. Treated sewage conforming to GPCB norms shall be utilized within premises for gardening & flushing purpose at the maximum extent possible. Only remaining quantity of treated sewage shall be disposed off through drainage line of AMC.
16. A proper logbook of STP operation and also showing the quantity of treated sewage utilization within premises & quantity of treated sewage discharged into the drainage line shall be maintained and furnished to the GPCB from time to time.
17. Dual plumbing system with separate tanks and lines shall be provided for utilization of treated sewage for flushing.
18. No bore well shall be constructed and existing bore well/s, if any, shall be either sealed or converted into a recharge well.
19. Rain water harvesting from rooftop and paved areas and ground water recharge through 2 nos. of percolation wells shall be carried out as per the details submitted. Before recharging the runoff, pre-treatment must be done to remove suspended matter.

A.2.2 AIR:

20. A D. G. set (125 KVA) proposed as backup power shall be of enclosed type and confirm to prescribe standards under EPA rules. Necessary acoustic enclosures shall be provided at diesel generator set to mitigate the impact of noise.
21. The exhaust of the D. G. Set shall be at least 3 m above roof top.
22. The gaseous emissions from the D.G. Sets shall conform to the standards prescribed under EPA rules as amended from time to time. At no time, the emission levels shall go beyond the stipulated standards.

A.2.3 SOLID WASTE:

23. The solid waste generated shall be properly collected and segregated at source. The biodegradable waste shall be converted into useful end product by treating it into the proposed onsite Organic Waste Converter and the recyclable waste shall be sold to vendors whereas the other garbage shall be disposed off properly as per the provisions made by the AMC.

A.2.4 SAFETY AND WELFARE:

24. Project Proponent shall obtain fire safety certificate / Fire No-Objection Certificate (NOC) from the concern authority as per the prevailing Rules / Gujarat Fire Prevention and Life Safety Measures Act, 2016.
25. Fire fighting facilities like Fire Extinguisher, First Aid Hose Reel, Wet riser, Yard Hydrant, Fire Alarm, Automatic detection and Alarm System, Automatic Sprinkler system in Basement are installed, provided number of sets of pumps each consisting of two electric and one diesel pump, terrace water tanks of 20 KL capacity at each block, underground water tank of 400 KL total capacity, smoke detectors etc shall be provided. A lightning arrester will



be installed and properly earthed.

26. Staircase shall be provided: 1 nos of 2 mts width in each block. All the staircases shall open out at ground level from the highest point of building [with access from each floor] for emergency evacuation. 2 nos of lifts shall be provided in each building.
27. Provision for adequate air changes per hour in the basement shall be made so as to avoid build-up of CO in the area.
28. Car park exhaust system equipped with CO (Carbon Monoxide) sensor shall be provided to ensure operation of exhaust fans as CO concentration levels.
29. Clear peripheral margin space of adequate width, in accordance with the concerned local bye-laws, shall be provided for unobstructed & easy movement of vehicles in case of emergency.
30. Sanitation facilities, drinking water & tap water, sewage disposal facility, first aid box, free medicines, doctor service, adequate PPEs etc. shall be provided for workers.

A2.5 PARKING / TRAFFIC CONGESTION:

31. Minimum parking space of 8931.82 m² (274 CPS) [8294.2 m² in Basement + 587.72 m² in Hollow Plinth + 50.40 m² in open area] shall be provided as proposed.

A 2.6 ENERGY CONSERVATION:

32. Energy conservation measures viz. maximum use of natural lighting through architectural design, energy efficient motors & pumps, water efficient taps, solar lights in open & solar street light, 112 KW solar power generation, use of aerated blocks & RMC, use of LED lighting fixtures and low voltage lighting, roof-top thermal insulation etc. shall be implemented as proposed.

A 2.7 GREEN BELT :

33. Green belt area of 575.93 m² comprising of 216 m² tree covered area with 90 trees within premises shall be developed as proposed. The other open spaces inside the plot shall be suitably landscaped and covered with vegetation of indigenous tree species.

B. GENERAL CONDITIONS :

B1. PRE -CONSTRUCTION AND CONSTRUCTION PHASE:

34. Mitigation of flood measures shall be undertaken. Height of the plinth and ramps will be increased so that flood water does not enter basement.
35. Project proponent shall explore possibilities to reuse the treated waste water for gardening and floor washing.
36. Roads leading to or at construction site must be paved and blacktopped (i.e. – metallic roads).
37. No excavation of soil shall be carried out without adequate dust mitigation measures in place.
38. Grinding and cutting of building materials in open area shall be prohibited.
39. Construction material and waste should be stored only within earmarked area and road side storage of construction material and waste shall be prohibited.
40. Construction and demolition waste processing and disposal site shall be identified and required dust mitigation measures be notified at the site.
41. Dust mitigation measure shall be displayed prominently at the construction site for easy public viewing.
42. Environment Management Cell shall be formed, which shall supervise and monitor the environment related aspects of the project during construction and operational phases in addition to observance of Gujarat Building and other Construction Workers (Regulation of Employment & Conditions of Service) Rules 2003.
43. Prior permission from the competent authority shall be obtained for cutting of the existing trees before site preparation work is commenced.
44. Water demand during construction shall be reduced by use of curing agents, super plasticizers and other best construction practices.
45. Wind – breaker of appropriate height i.e. 1/3rd of the building height and maximum up to 10 meters shall be provided. Individual building within the project site shall also be provided with barricades.
46. Regular water sprinkling shall be done in vulnerable areas for controlling fugitive emission.
47. No uncovered vehicles carrying construction material and waste shall be permitted.
48. No loose soil or sand or construction & demolition waste or any other construction material that cause dust shall be left uncovered. Uniform piling and proper storage of sand to avoid fugitive emissions shall be ensured.
49. Structural design of the project shall strictly adhere to the seismic zone norms for earthquake resistant structures.
50. The planning, designs and construction of all buildings shall be such as to ensure safety from fire.
51. The project proponent shall ensure maximum employment to the local people.



52. All required sanitary and hygienic measures shall be provided before starting the construction activities and to be maintained throughout the construction phase.
53. Provision shall be made for housing of construction labor within the site with all necessary infrastructure and facilities such as fuel for cooking, mobile toilets, mobile STP, safe drinking water, medical healthcare, crèches, electricity & ventilation, canteen, rest rooms, safe disposal system for garbage, first aid, medical and emergency facilities etc. to ensure that they do not ruin the existing environmental condition. The housing may be in the form of temporary structures to be removed after completion of the project.
54. Adequate personal protective equipments shall be provided to the construction workers to ensure their safety and the project proponent shall ensure its usage by the labours.
55. First Aid Box shall be made readily available in adequate quantity at all the times.
56. Training shall be given to all workers on construction safety aspects.
57. The project proponent shall strictly comply with the Building and other Construction Workers'(Regulation of Employment & Conditions of Service) Act 1996 and Gujarat rules made there under and their subsequent amendments.
58. The overall noise level in and around the project area shall be kept well within the prescribed standards by providing noise control measures including acoustic insulation, hoods, silencers, enclosures vibration dampers etc. on all sources of noise generation.
59. Ambient noise levels shall conform to residential standards both during day and night. Incremental pollution load on the ambient air and noise quality shall be closely monitored during construction phase
60. The noise generating equipments, machinery and vehicles shall not be operated during the night hours and shall be maintained properly to avoid generation of high noise due to wear and tear.
61. Use of diesel generator sets during construction phase shall be strictly with acoustic enclosure and shall conform to the EPA Rules for air and noise emission standards.
62. Safe disposal of wastewater and municipal solid wastes generated during the construction phase shall be ensured.
63. All topsoil excavated during construction activity shall be used in horticultural / landscape development within the project site.
64. Construction materials and debris shall be properly stored and handled to avoid negative impacts such as air pollution and public nuisances by blocking the roads and public passages.
65. Construction debris shall be reused in construction of roads, levelling the site etc. Waste packaging material (like used cement bags, waste paper, cardboard packing material), metal scraps etc. shall be sold to recyclers or shall be sent to the nearest municipal solid waste landfill site.
66. Excavated earth to be generated during the construction phase shall be utilized within the premises to the maximum extent possible and balance quantity of excavated earth shall be disposed off with the approval of the competent authority after taking the necessary precautions for general safety and health aspects. Disposal of the excavated earth during construction phase shall not create adverse effect on neighbouring communities.
67. Provisions of Construction & Demolition Waste Management Rules-2016 shall be strictly adhered to.
68. Vehicles hired for bringing construction material at the site shall be in good conditions and conform to applicable air and noise emission standards and shall be operated only during day time and non-peak hours.
69. Project proponent shall ensure use of eco-friendly building materials including fly ash bricks, fly ash paver blocks, Ready Mix Concrete [RMC] and lead free paints in the project.
70. Fly ash shall be used in construction wherever applicable as per provisions of Fly Ash Notification under the E.P. Act, 1986 and its subsequent amendments from time to time.
71. Use of glass shall be minimal and only low emissive glass shall be used in the project to reduce the electricity consumption and load on air conditioning.

B2. OPERATION PHASE AND LIFE TIME:

72. PP shall take all require mitigation measures so as to comply with the ambient noise levels standards of the residential area during day and night time as per Noise Pollution (Control and Regulation) Rules, 2000.
73. PP shall take all require dust mitigation measures so as to comply with the National Ambient Air Quality standards 2009 and shall provide adequate budget for the same.
74. The project proponent shall prepare, display at prominent place in the construction site and implement the fire and safety SOPs for fall protection, ladders and staircase, scaffolds, trenching and excavation, electrical safety, crane operations, occupational noise mitigation procedure, welding and cutting



including provision of PPE kits etc.

75. Project proponent or the maintenance society to whom the project has been handed over shall ensure allocation of parking to each and every member of the society as per the rules as soon as possible not later than 3 months and display the same in the society notice board and inform the local authorities like Municipal Corporation, UDA, RERA/ SEIAA and ensure proper parking without fail.
76. Proponent shall maintain traffic system within the premises to avoid congestion and unsafe parking in the premises, particularly safety parameters including fire, safety, installation of fire equipment's, house pipes etc. with due care to regular maintenance check-up and hold mock drills from time-to-time. Any damage to the greenbelt area must be avoided unless approved by the competent authority.
77. The PP shall also ensure notarized undertaking from the maintenance society at the time of hand over to comply with all the conditions of EC scrupulously failing which the EC will be liable to be withdrawn.
78. Provision of fire lift may be provided, additional lift may be provided in high rise building for safety.
79. Regular maintenance of leakages of water and waste water shall be carried out.
80. When the property is handed over to society, the proponent should ensure by notarized undertaking to abide by all the conditions of EC and copy of the such transfer letter with notarized undertaking shall send to GPCB / SEAC & SEIAA.
81. The project proponent shall provide water pumping arrangement and especially when the discharge in to municipal drainage, for annual inspection and cleaning to avoid inundation and surface water pollution and health hazard.
82. The proponent shall ensure that the occupants of the society are allotted parking space as approved in EC order and put-it on display the allotment of parking to the occupants in the society maintenance of it.
83. On the project proponent shall ensure the distance criteria is properly followed while undertaking construction in consistence with the existing directions of local self government bodies.
84. The orders shall mention the limit of floors given in the proposal. Any deviation from that could attract withdrawal of the EC as a violation case.
85. If there is Basement parking in proposed in the project then they should always maintain clean, free from hanging electric wires and provide adequate light.
86. Separate Entries and Exits shall be provided to the project on the approach road.
87. Separate Entry and Exit to the basement shall be provided.
88. Explore possibilities of provision of Electric vehicle charging points in the parking area.
89. Project Proponent shall provide adequate fund for Environment Monitoring and Staff training in the Environment Management Plan.
90. In Municipal Corporation before approval of plan layout it shall be ensure that the project proponent has projected the space for tree plantation with tree guard in a space between municipal road & their premises.
91. The project proponent shall take written undertaking from the society association to maintain compliance of conditions pertaining to tree plantation, maintaining hygienic condition in and around the premises for building construction projects.
92. Notwithstanding the provision of EMP/CER, the proponent shall incur full expenditure as may be required at the time of execution of the project.
93. The project proponent shall take written undertaking from the Society Association to ensure compliance of environment conditions when it is handed over to them.
94. Project proponent shall ensure fire safety and safe lift installation by getting the due certification from competent authority.
95. Project proponent shall take proper maintenance of electrification with respect to human safety.
96. Project Proponent shall prominently display the copy of Environment Clearance at site.
97. Tree Plantation prescribed in the EC shall be maintained by the Society Association.
98. Proponent as well as successor society shall maintain hygienic conditions and cleanliness in and around the project site all the time.
99. Project proponent shall ensure fire safety by getting the due certification from competent authority.
100. The design of building has to be earthquake resistant & duly certified by competent structural engineer of competent authority.
101. The project proponent shall explore the possibilities & adopt mitigation measures to minimize the impact of project with reference to Urban Heat Island (UHI) Phenomena.



102. The project proponent shall allocate funds as may be required for the compliance of Environment Management plan & CER activity proposed at the time of execution of the project.
103. Project proponent shall adopt the 3R concept of Reduce, Reuse and Recycle and while handing over the project to Maintenance Society shall ensure the compliances as required.
104. Low water consuming devices shall be provided. Fixtures for showers, toilet, flushing and drinking shall be of low flow either by use of aerators/ diffusers or pressure reducing devices etc.
105. A water meter shall be installed on rain water harvesting & ground water recharge well system & compliance report of the same shall be submitted to concerned authorities.
106. Used oil shall be sold only to the registered recycler.
107. Provisions of Solid Waste Management Rules-2016 shall be strictly adhered to.
108. Requisite fire fighting facilities as per the requirement of NBC and Gujarat Fire Prevention and Life Safety Measures Act-2013 along with the rules & regulations made there under shall be provided.
109. Underground fire water storage tanks and terrace water storage tanks of adequate capacity shall be provided as proposed. Adequate provision shall be made to ensure that water from the Fire Water Tank shall not be used for any other purpose.
110. Dedicated power back up system shall be provided in the case of power failure & emergency of fire water pumps.
111. First Aid Box shall be made readily available in adequate quantity at all the times.
112. Main entry and exit shall be separate and clearly marked in the facility
113. Necessary emergency lighting system along with emergency power back up system shall be provided. Further, necessary auto glow signage at all appropriate places shall be provided to guide the people towards exits and assembly points during emergency.
114. Sufficient peripheral open passage shall be kept in the margin area for free movement of fire tender/ emergency vehicle around the premises.
115. The overall noise level in and around the project area shall be kept well within the prescribed standards by providing noise control measures including acoustic insulation, hoods, silencers, enclosures vibrations dampers etc. on all sources of noise generation including D.G.Sets. The ambient noise levels shall conform to the standards prescribed under the Environment (Protection) Act and Rules.
116. The area earmarked for the parking shall be used for parking only. No other activity shall be permitted in this area.
117. Traffic congestion near the entry and exit points from the roads adjoining the proposed project site shall be avoided. No public space including the service road shall be used or blocked for the parking.
118. The project proponent shall install energy efficient devices, appliances, motors, and pumps conforming to the Bureau of Energy Efficiency norms.
119. The transformers and motors shall have minimum efficiency of 85%.
120. Only variable frequency motor drives shall be used in project.
121. Application of solar energy shall be incorporated for illumination of common areas, lighting for gardens and street lighting. In addition the provision for solar water heating system shall also be provided.
122. Use of glass shall be minimal to reduce the heat island effect as well as to reduce the electricity consumption.
123. The area earmarked as green area shall be used only for plantation and shall not be altered for any other purpose.
124. Drip irrigation/low volume, low angle sprinkler system shall be used for the lawns and other green area including tree plantation.
125. The project proponent shall inform to SEAC / SEIAA regarding the transfer of management responsibility to the Society / Association to be formed for the proposed project with all the supporting documents. The Society / Association formed for further management of the proposed project shall be responsible for compliance of all the conditions stipulated in the Environmental Clearance order.
126. Environmental Clearance granted for the project on the basis of documents related to land possession submitted shall become invalid in case the actual land for the project site turns out to be different from the land considered at the time of appraisal of the project and mentioned in the EC.
127. All other statutory clearances such as N.A. permission, approvals for storage of diesel from PESO, Fire Department, Airports Authority of India etc., if applicable, shall be obtained by the project proponent from the competent authorities.




128. All the conditions as may be stipulated in the N.A. order, Development permission, Building Use permission, NOC obtained from Fire Department etc. shall be strictly complied with.
129. The project management shall also comply with all the environment protection measures, risk mitigation measures and safeguards proposed by them.
130. All the commitments / undertakings given to the SEAC during the appraisal process for the purpose of environmental protection and management shall be strictly adhered to.
131. The project proponent shall also comply with any additional condition that may be imposed by the SEAC or the SEIAA or any other competent authority for the purpose for the environmental protection and management.
132. All the terms & conditions prescribed in the amendment of EIA Notification – 2006 published by the MoEF&CC vide its Notification No. S.O. 3999(E) dated 9th December, 2016 shall be complied with letter & spirit.
133. The project proponent shall strictly comply with the Gujarat Building and other Construction Workers' (Regulation of Employment & Conditions of Service) Rules 2003 as well as Gujarat Lifts & Escalators Rules as amended from time to time.
134. No further expansion or modifications in the project likely to cause environmental impacts shall be carried out without obtaining prior Environment Clearance from the concerned authority.
135. The above conditions shall be enforced, inter-alia under the provisions of the water (Prevention & Control of Pollution) Act, 1974, Air (Prevention & Control of Pollution) Act, 1981, the Environment (Protection) Act 1986 and the Hazardous Wastes (Management Handling and Tran boundary) Rules, 2008, Building and Other Construction Workers' (Regulation of Employment & Conditions of Service) Act-1996, The Gujarat Lifts and Escalators Act-2000 along with their amendments and rules.
136. The project proponent shall obtain the requisite permissions / clearance under the provisions of the Indian Forest Act 1927, Forest Conservation Act 1980 and Wildlife (Protection) Act 1972.

B3. OTHER:

137. The project proponent shall allocate the separate fund as committed before SEAC for activities like Solar street lights in Singarwa & Bhulavadi Village Rain Water Harvesting Structures in Singarwa & Bhulavadi Village (04 nos.) Distribution of green bins and blue bins & Organic Waste Converter OWC (2 Nos.) in Singarwa & Bhulavadi Village. Activities proposed under Corporate Environment Responsibility (CER) shall be part of Environment Management Plan (EMP) as per the MoEF&CC's OM no. F. No. 22-65/2017-IA.III dated 30.09.2020. The said activities shall be completed within 3 years from the commencement of the project. The CER shall be monitored and the monitoring report shall be submitted to the regional office of MoEF&CC as a part of half-yearly compliance report and to the District Collector. The monitoring report shall be posted on the website of the project proponent.
138. The project authorities shall earmark adequate funds to implement the conditions stipulated by SEIAA as well as GPCB along with the implementation schedule for all the conditions stipulated herein. The funds so provided shall not be diverted for any other purpose.
139. The project proponent shall adhere to provisions made for Corporate Environment Responsibility "CER" in Office Memorandum dated 01/05/2018 by Ministry of Environment, Forests & Climate Change and its amendments from time to time in a letter and spirit.
140. The applicant shall inform the public that the project has been accorded environmental clearance by the SEIAA and that the copies of the clearance letter are available with the GPCB and may also be seen at the Website of SEIAA/ SEAC/ GPCB.
141. It shall be mandatory for the project management to uploaded half yearly compliance report on website of Gujarat Real Estate Regulatory Authority, on 1st June and 1st December of each calendar year.
142. The project authorities shall also adhere to the stipulations made by the Gujarat Pollution Control Board.
143. The project authorities shall inform the GPCB, Regional Office of MoEF&CC and SEIAA about the date of financial closure and final approval of the project by the concerned authorities and the date of start of the project.
144. The SEIAA may revoke or suspend the clearance, if implementation of any of the above conditions is not found satisfactory. This environmental clearance is valid for ten years from the date of issue.
145. Submission of any false or misleading information or data which is material to screening or scoping or appraisal or decision on the application makes this environment clearance cancelled.

B4. COMPLIANCE OF ENVIRONMENT CLEARANCE/REPORTING/ADMINISTRATION/APPEAL:

146. Project proponent shall inform to all the concerned authorities including Municipal Corporation, district collector, UDA & RERA and shall also give wide publicity through advertisement in minimum two local newspapers within seven days, about the environment clearance order accorded.



147. Project proponent shall appoint a key person in the organization who shall be responsible for compliance of above condition fully on behalf of the proponent. It will not mean that appointing a key person will exempt the project proponent from the responsibility of compliance. Any change in key person shall immediately be informed to SEIAA and all concerned authorities.
148. Designated key person shall submit six monthly compliance report to SEIAA/SEAC, MOEF&CC, GPCB and Nodal Department of the Government.
149. Prior EC is granted is subject to the proponent receiving all statutory permission / clearances / certificates and membership of respective agencies / authorities failing which this provisional EC will stand withdrawn. Proponent shall inform progress from time to time, in six monthly compliance report to MOEFCC / SEIAA / SEAC/ GPCB.
150. The concern authority like Municipal Corporation, district collector, UDA & RERA or any authority or officer authorized by MOEF&CC/SEIAA can inspect the site of the project and all the facilities, for verification of compliances of environment clearance conditions.
151. In case of violation reported upon, the project proponent shall be responsible for all the legal actions as per Environment Protection Act, 1986 including SEIAA may cancel, withdraw or keep in abeyance, the environment clearance accorded.
152. Any person including the project proponent affected by this environment clearance order may file appeal to Honorable National Green Tribunal West Zone branch, Pune, preferably within a period of thirty days from the date of issue of environment clearance as prescribe under section 16 of National Green Tribunal Act 2010.
153. All complains and public grievance or representations may be addressed to SEIAA/SEAC in the email addresses (a) msseiaagj@gmail.com & (b) seacgujarat@gmail.com.


(NISCAL JOSHI)
Member Secretary

Issued to:

**Nest Infinity
Survey No. 100, F.P. No. 21,
T.P.S. No. 119, At Nikol,
Ta. Asarva, Dist. Ahmedabad.**

Copy to:-

1. The Secretary, SEAC, C/O. G.P.C.B. Gandhinagar - 382010.
2. The Additional Chief Secretary, Forests & Environment Department, Govt. of Gujarat, Block 14, 8th floor, Sachivalaya, Gandhinagar-382010.
3. The Chairman, Central Pollution Control Board, Parivesh Bhavan, CBD -cum-Office Complex, East Arjun Nagar, New Delhi-110032
4. Scientist C, Integrated Regional Office, Ministry of Environment and Forests, Aranya Bhavan, Sector-10, Gandhinagar - 382010.
5. Monitoring Cell, Ministry of Environment and Forests, Paryavaran Bhavan, CGO Complex, New Delhi-110003.
6. The Member Secretary, Gujarat Pollution Control Board, Paryavaran Bhavan, Sector-10 A, Gandhinagar-382010
7. Select File



Signature Not Verified

Digitally signed by Shri Prakash K. Majmudar
Member Secretary