

RERA CARPET AREA CAL. (1ST TO 7TH FLOOR)

BLOCK-A 101 TO 601, 102 TO 602 103 TO 603			
3.51X5.30	=	18.60	
1.68X1.75	=	2.94	
3.58X1.52	=	5.44	
5.87X6.63	=	38.92	
3.62X6.52	=	23.60	= 89.50 (CARPET)
2.17X1.52	=	3.30	
3.51X1.10	=	3.86	= 7.16 (WASH & BALC.)
TOTAL			= 96.66 SQ.MT.

BLOCK-B 101 TO 701, 102 TO 702			
3.51X5.30	=	18.60	
1.68X1.75	=	2.94	
3.58X1.52	=	5.44	
5.87X6.63	=	38.92	
3.62X6.52	=	23.60	= 89.50 (CARPET)
2.17X1.52	=	3.30	
3.51X1.10	=	3.86	= 7.16 (WASH & BALC.)
TOTAL			= 96.66 SQ.MT.

BLOCK-B 103 TO 603			
3.51X5.30	=	18.60	
1.68X1.75	=	2.94	
3.58X1.52	=	5.44	
5.87X6.63	=	38.92	
3.62X6.29	=	22.77	
1.68X0.23	=	0.39	= 89.06 (CARPET)
2.17X1.52	=	3.30	
3.51X1.10	=	3.86	= 7.16 (WASH & BALC.)
TOTAL			= 96.22 SQ.MT.

RERA CARPET AREA TABLE (BLOCK-A)

FLOOR	UNIT NO	RERA CARPET AREA	RERA WASH & BALC. AREA
1ST TO 6TH FL.	101 TO 601	89.50	7.16
	102 TO 602	89.50	7.16
	103 TO 603	89.50	7.16

RERA CARPET AREA TABLE (BLOCK-B)

FLOOR	UNIT NO	RERA CARPET AREA	RERA WASH & BALC. AREA
1ST TO 6TH FL.	101 TO 601	89.50	7.16
	102 TO 602	89.50	7.16
	103 TO 603	89.06	7.16

RERA CARPET AREA TABLE (BLOCK-B)

FLOOR	UNIT NO	RERA CARPET AREA	RERA WASH & BALC. AREA
7TH FL.	701	89.50	7.16
	702	89.50	7.16



STAIR CABIN & TERRACE PLAN



7TH FLOOR PLAN



1ST TO 6TH FLOOR PLAN

GR. FLOOR/LAYOUT PLAN	SHEET NO:- 3/4

PLAN SHOWING PROPOSED RESIDENTIAL BUILDING ON
F.P. NO: 313/2, O.P. NO: 313, SUR. NO: 1804/1,
T.P.S. NO:3 (DAHEGAM),
MOJE: DAHEGAM, TAL.: / DIST: GANDHINAGAR.

SCALE : 1CM = 1.0M.

ZONE : RESIDENTIAL-I (R1)
USE : RESIDENTIAL (DW3)

BUILT UP AREA CALCULATION

GR. TO 6TH FLOOR
47.15X18.52 = 873.22
LESS
(1) 2X3.73X5.87 = 43.79
(2) 2X3.87X3.42 = 26.47
(3) 7.54X1.75 = 13.20
(4) 3.73X5.04 = 18.80
(5) 11.28X1.87 = 21.09
(6) 1.94X2.10 = 4.07
(7) 3.73X3.16 = 11.79 = 139.21

NET BUILT UP AREA ON GR. TO 6TH FLOOR = 734.01 SQ.MT.

FSI AREA CALCULATION

1ST TO 6TH FLOOR
NET B.A. ON 1ST TO 6TH FL. = 734.01
LESS
(A) 2X3.99X3.67 = 29.29
(B) 2X3.87X3.05 = 23.61
(C) 2X3.73X2.00 = 14.92
(D) 2X3.85X2.27 = 17.48
(E) 3.62X3.39 = 12.27
(F) 1.65X3.39 = 5.59
(G) 1.97X1.64 = 3.23 = 106.39

NET FSI AREA ON 1ST TO 6TH FLOOR = 627.62 SQ.MT.

BUILT UP AREA CALCULATION

7TH FLOOR
26.33X15.10 = 397.58
LESS
(1) 2X3.73X8.36 = 62.37
(2) 7.54X6.72 = 50.67
(3) 1.71X4.97 = 8.50
(4) 3.85X2.45 = 9.43
(5) 1.65X6.83 = 11.27
(6) 2X2.10X1.64 = 6.89 = 149.13

NET BUILT UP AREA ON 7TH FLOOR = 248.45 SQ.MT.

FSI AREA CALCULATION

7TH FLOOR
NET B.A. ON 7TH FL. = 248.45
LESS
(A) 4.10X3.67 = 15.05
(B) 3.87X3.05 = 11.80
(C) 3.73X2.00 = 7.46
(D) 3.85X2.27 = 8.74 = 43.05

NET FSI AREA ON 7TH FLOOR = 205.40 SQ.MT.

BUILT UP AREA CALCULATION

STAIR CABIN
2X4.10X8.70 = 71.34
2X3.89X6.25 = 48.63 = 119.97 SQ.MT.

L.M.R. & O.H.W.T.
2X3.89X4.50 = 35.01
2X4.10X3.21 = 26.32 = 61.33 SQ.MT.

SCHEDULE OF OPENING

DOOR	WINDOWS	VENT
D =1.00X2.10	W =1.80X1.20	V =0.60X0.60
D1=0.90X2.10	W1=0.75X1.20	
D2=0.75X2.10		
SD=3.30X2.10		

RCC STAIR DETAIL
WIDTH=1.52M
TREAD=0.25M
RISER=0.16M

COLOUR NOTE -
- PLOT BOUNDARY
- PROPOSED WORK
- PROPOSED DRAINAGE

NISHIL M. SHAH
(BE CIVIL)
F/4, Bhaikakanagar, Thaltej, Ahmedabad - 380059.
AUDA/COW-I/716
CLERK OF WORKS

NISHIL M. SHAH
(BE CIVIL)
F/4, Bhaikakanagar, Thaltej, Ahmedabad - 380059.
AUDA/ENGG/1015
ENGINEER.

NISHIL M. SHAH
(BE CIVIL)
F/4, Bhaikakanagar, Thaltej, Ahmedabad - 380059.
AUDA/SD-II/157
STRU.ENGINEER.

OWNER

AUDA R. NO.-DEV-885
29 TULSI SOCIETY C.T.M. AHMEDABAD
SHREE RANG DEVELOER
DEVELOPER

ધ્યાન ખેંચ :-
કોમ્પ્લેક્ષ લે-આઉટ લેજર સોફ્ટીક ટેક તથા સાઇટ ની સાઇજ તથા સંખ્યા નેશનલ બિલ્ડીંગ કોડ (આઈ.એસ.-૨૪૭૦) તથા સિવિલ એન્જીનીયરીંગ હેન્ડ બુક બાબત-ભલ્યા મુજબ રાખવામાં આવેલ છે તે અનુસાર અરજદાર જમીન માલિકે સ્થાયમ્ત બાંધકામ કરવાનું રહેશે.

ધ્યાન રાખવા :
વિકાસ પરવાનગી મેળવેલ બાંધકામ બાબતે જુદા જુદા તબક્કે ખોદાણ પ્લીન્થ લેવલ (તથા દરેક) સ્લેબ લેવલે ઓફા કરેલી તબક્કથી રથળ નિરીક્ષણ કરાવી તબક્કાવાર પરિસ્થિતિની પકાસણી કરાવી જે તે બાંધકામ આપ્યાંક વિકાસ પરવાનગી મુજબનું છે. તે મતલબનું પ્રમાણપત્ર મેળવ્યા બાદજ આગળના તબક્કાનું બાંધકામ કરવાનું રહેશે.

ધ્યાન રાખવા
મંજુર થયેલ નકશાઓની નકલનો ૧ સેટ સ્થળ પર પ્રસિધ્ધ કરવાનો રહેશે

ધ્યાન રાખવા
બાંધકામ પૂર્ણ થયા બાદ બાંધકામ નો ઉપયોગ શરૂ કરવાં પહેલા નિયમાનુસાર અરજી મકાનના વપરાશ પ્રમાણપત્ર મેળવવાનું કરવાનું રહેશે.

ધ્યાન રાખવા
તા..... ના રોજ માલિક ઓર્ગેનાઈઝ આર્કીટેક્ટ તથા સ્ટ્રકચરલ એન્જીનીયરે આપેલ બાંહેધરી પત્રમાં દર્શાવેલ તમામ શરતોનું ચુસ્તપણે પાલન કરવાનું રહેશે.

Final Plan boundary and allotment of final plot is Subject to Variation by Town Planning Officer

Owner is fully responsible For open marginal Space and road line Portion.

The permission is valid only in the DP/TPS remains unaltered and further that the permission shall stand revoked as soon as there is change in DP/TPS with reference to the land under reference.

અમદાવાદ શહેરી વિકાસ સત્તામંડળ
રૂબરૂ સહી કરાવેલ છે
આસીસ્ટન્ટ / કલાર્ક

APPROVED
As amanded by Red (Colour) Subject to the condition as mentioned in this office Letter PRM No. 12/2/2020
Dated.....
New Approved on 6 AUG 2020
No 195

DISPATCH BY

Assistant Town Planner
Ahmedabad Urban Development Authority
AUTHORITY Ahmedabad.

Senior Town Planner
Ahmedabad Urban Development Authority
Ahmedabad.