

R.C.C. COLUMN FOOTING SECTION AS PER STRUCTURAL DESIGN.

FLOOR AREA TABLE :-		
FLOOR	USE	AREA
	RESI.	RESI.
GR. FLOOR	16	605.53
1st. FLOOR	---	602.41
2nd. FLOOR	---	259.89
TOTAL	16	1467.83

BUILT UP AREA TABLE	
FLOOR	AREA
GR. FLOOR	771.94
1st. FLOOR	771.94
2nd. FLOOR	514.16
TOTAL	2058.04

F.S.I AREA TABLE	
FLOOR	AREA
GR. FLOOR	771.94
1st. FLOOR	771.94
2nd. FLOOR	514.16
TOTAL	2058.04

BUILT UP & F.S.I. AREA CALC. ON TYPICAL FLOOR GR. & 1st. FLOOR

63.25 X 13.71 X 1 = 867.16

LESS :-

(01) 2.42 X 2.72 X 2 = 13.16

(02) 4.31 X 2.72 X 7 = 82.06

TOTAL = 95.22

867.16 - 95.22 = 771.94

NET BUILT UP AREA = 771.94

BUILT UP & F.S.I. AREA CALC. ON TYPICAL FLOOR 2nd. FLOOR

63.25 X 10.19 X 1 = 644.52

LESS :-

(01) 2.42 X 2.72 X 2 = 13.16

(02) 4.31 X 2.72 X 7 = 82.06

(03) 3.16 X 0.75 X 2 = 4.74

(04) 5.79 X 0.75 X 7 = 30.40

TOTAL = 130.36

644.52 - 130.36 = 514.16

NET BUILT UP AREA = 514.16

OPENING SCHEDULE :-

D = 1.07 X 2.13 D2 = 0.76 X 2.13 W2 = 1.61 X 0.91
D1 = 0.91 X 2.13 W = 2.08 X 1.22 W3 = 1.29 X 0.91
W1 = 1.93 X 0.91 W4 = 1.13 X 0.91
V = 0.60 X 0.60

R.C.C. STAIR DETAIL

WIDTH = 1.00 TREAD = 0.25 RISER = 0.15

COLOUR NOTE :-

PROP.WORK PROP.DRAIN





2nd. FLOOR PLAN



1st. FLOOR PLAN



GR. FLOOR PLAN

PLAN SHOWING RESI. BUILDING ON F.P. NO. :- 44/2 ,O.P. NO. 44 , OLD SUR. NO. - 81 & NEW SUR. NO. - 448, DRAFT T.P.S.:- 118 (SINGARVA) MOJE : SINGRVA, TAL.:- DASKROI , DIST : AHMEDABAD.

BLOCK :- A

SHEET NO. :- 02

SCALE : 1 CM = 1.00 MT ZONE : R2 USE : RESI. (DWELLING - II)

PROP. BUILT UP AREA ON GR. FLOOR	771.94
PROP. BUILT UP AREA ON 1st FLOOR	771.94
PROP. BUILT UP AREA ON 2nd. FLOOR	514.16
TOTAL BUILT UP AREA	**2058.04**
PROP. F.S.I. AREA ON GR. FLOOR	771.94
PROP. F.S.I. AREA ON 1st. FLOOR	771.94
PROP. F.S.I. AREA ON 2nd. FLOOR	514.16
TOTAL BUILT UP AREA	**2058.04**

NOTES:-

ENGINEER IS FULLY RESPONSIBLE FOR LEAVING OPEN SPACE AND MARGIN.
THE DEPTH AND POSITION OF EXISTING MUNICIPAL MANHOLE IS VERIFIED ME ON SITE AND PREMISES GATES DRAINAGE CONNECTION.
IT IS CERTIFY THAT ACCORDING TO GDCR 2021 ALL REQUIREMENTS OF THE BUILDING ARE CHECKED AND NECESSARY ACTIONS ARE TAKEN.
IT IS CERTIFY THAT ACCORDING TO THE CLAUSE NO. 4.5.3 OF THE GDCR, THE STRUCTURE OF THE BUILDING IS DESIGN AS PER THE NORMS OF THE INDIAN STANDARDS.
DESIGN OF STAIRCASE AND RAILING IS PROVIDED AS PER THE PROVISION OF THE CLAUSE NO. 23.1.12 AND 23.14 AND 24.6 OF GCDR 2021
WATER TANK IS PROVIDED AS PER THE PROVISION OF THE CLAUSE NO. 23.6 OF GDCR 2021
SEPARATE LEETER BOX IS PROVIDED AT GROUND LEVEL FOR EACH UNIT.
ELECTRICAL INFRASTRUCTURE SHALL BE PROVIDED AS PER CLAUSE NO. 23.11
DRAINAGE FACILITY IS PROVIDED AS PER THE CLAUSE NO. 23.10
ENTRANCE OF THE BUILDING IS PROVIDED AS PER THE CLAUSE NO. 23.1.7 OF GDCR 2021
THE PAVING OF BUILDING UNTUFVIL PLOT AS PER THE PROVISION OF THE CLAUSE NO. 23.1.4 OF GDCR 2021
THE STRUCTUE OF THE BUILDING IS AS PER THE NORMS OF THE SPECIFIED IN THE INDIAN STANDARD AND TAKE NACESSARY ACTION FOR THE STRUCTRAL SAFETY DURING THE CONSTRUCTION
RAIN WATER STORAGE TANK AND RAIN WATER HAJVESTING SYSTEM IS PROVIDED AS PER THE CLAUSE NO. 27.2 OF GCDR 2021
COMMUNITY BIN PROVIDED AS PER THE PROVISION OF THE CLAUSE NO. 27.3 OF GDCR 2021
TREE PLANTATION IS PROVIDED AS PER THE CLAUSE NO. 27.5 OF GDCR 2021
SOLAR WATER HEATING SYSTEM IS PROVIDED AS PER THE CLAUSE NO. 27.6 OF THE GDCR 2021
MAINTANANCE AND UPGRADATION OF BUILDING IS AS PER CHAPTER NO. 29 OF GDCR 2021.

SAHYOG DEVELOPERS
Patel Jayantibhai Laxmanbhai
04, New Sarita Society, L.B.S. Road, Nr. Harshed Colony, Narayan Nagar, Ahmedabad-382350
Reg. No. AUDA/DEV/861
DEVELOPER

For, Khodiyar Associates
Partner
OWNER

CHIRAGKUMAR P. NAKRANI (B.E. CIVIL)
A-101, Shantiniketan - 2, Nr. Pavilion, Nr. Rajhans Cinemas, New India Colony Road, Nikol, Ahmedabad-382350.
AUDA LIC NO. : ENGG - 01107
AUDA LIC NO. : COM-I-00794
ENGINEER / C.O.W.

A. Y. CHHIPA
B.E. (CIVIL) M.I.E.
STRUCTURAL ENGINEER
GRADE ONE
AUDA LICENCE NO.
SD-1/247
743/6, DADI BIBI MASJID MANZIL
PIRANPIR DARGAH,
RAIKHAD, AHMEDABAD-1
STR.ENGINEER

ખાસ નોંધ :-
ફ્રેમ્સ કે-આધિત સેમ્પ્ર સોલીક ટેક વધા સાધ્ર્ ની સાર્ફ્ર્ તથા સંખ્યા નેશનલ બિલ્ડીંગ કોડ (આઈ.એસ.-૨૪૫૦) તથા ફિસિલ સોલ્યુનીયરીંગ ધ્વર્ક ધુર્ક બાય-ખબ્બા મુજબ રાખવામાં આવેલ છે તે અનુસાર અરજદાર જમીન માલિકે સ્થાયમ્ર બાંધકામ ફરવાનું રહેશે.

ખાસ શરત :
ફિલ્મ પ્રધાનજી મેળવેલ બાંધકામ બાબતે જુદા જુદ્ર તબ્બ્રે ખેડાણ પ્રીન્ય લેવલ (તથા દરેક) સ્લેબ લેવલે અંકા કરેરી તરફથી સ્થળ નિરીક્ષણ કરાવી તબક્કાવાર પરિપ્રેક્ષિતની ચકાસણી કરાવી જે તે બાંધકામ અંગેનો ફિલ્મ પ્રધાનજી મુજબનું છે. તે મતલબનું પ્રમાણપત્ર મેળવ્યા બાદજ આગળના તબક્કાનું બાંધકામ કરવાનું રહેશે.

ખાસ શરત :
નકશામાં સૂચવવામાં આવેલ કામના પ્લોટનો કબ્જો જ્યાં સુધી ઝાર જમીનની માલિકો ઓકયાયરી ઓથોરીટીએ/તંત્રની ન રાય ત્યાં સુધી કોમન પ્લોટની જવાબ્રે / માલિકી સત્તામંડળની રહેશે.

ખાસ શરત
ત્ર.....ના રોજ માલિક ઓર્ગેનાઈઝ આર્કીટેક્ટ તથા સ્ટ્રકચરલ એન્જીનીયરે આપેલ બાંહેધરી પત્રમાં દર્શાવેલ તમામ શરતોનું ચુસ્તપણે પાલન કરવાનું રહેશે.

ખાસ શરત —
નકશામાં ચૂર્ણ થયા બાદ બાંધકામ ના ઉપયોગ થઇ શકતાં પહેલા નિયમાનુસાર અગ્નિથી મકાનના ઉપયોગ' પ્રમાણપત્ર મેળવવાનું' રહેશ્વાન છે

Final Plan boundary and allotment of final plot is Subject to Veriation by Town Planning Officer

ખાસ શરત
મંજુર થયેલ નકશાઓની નકલનો ૧ સેટ સ્થળ પર પ્રસિધ્ધ કરવાનો રહેશે

Owner is fully responsible for open marginal Space and road line Portion.

The permission is valid only to the DP/TPS remains unaltered and further that the permission shall stand revoked as soon as there is change in DP/TPS with reference to the land under reference.

APPROVED
As amanded by Red (Colour) Subject to the condition as mentioned in this office Letter PRM No. 4224 dated....6...SEP 2017
Note Approved by Chairman
No 489

DISPATCH BY
Assistant Town Planner
Ahmedabad Urban Development Authority
Ahmedabad.

Senior Town Planner
Ahmedabad Urban Development Authority
Ahmedabad.