

SECTION - AA

FIRE HYDRANT LEGEND		
SR.	SYMBOL	DESCRIPTION
1		FIRE HYDRANT PIPE MAIN
2		SLUICE VALVE
3		NON RETURN VALVE
4		COURT YARD HYDRANT VALVE
5		LANDING HYDRANT VALVE
6		HOSE BOX
7		FIRST AID HOSE REEL
8		AIR RELEASE VALVE
9		TWO WAY SHARES CONNECTION
10		RISE OR DROP



1. HYYDRANT SYSTEM:

ON/OFF switches located near the hose reel hose or hydrant outlet, at each floor the main FirePump at the underground water tank with a capacity to discharge 900 liters per minute at 3 bar. pressure as measured at the terrace level should be installed.
The Riser for the buildings exceeding 18 meters and above 18 meters height should not be of less than 100 mm. internal diameter. The riser should be connected to the bottom of the terrace tank with a stop valve and a NRV to act as a pump riser.
For buildings up to 15 storey 1500sq. meters floor area and if the building is divided into, two or more parts then each part should have a separate riser with all the fittings at floor level. Each floor should have one hydrant outlet with a coupling for attaching a 63 mm dia hose & 25 mm bore Hose-reel hose with 6 mm. SS. Shut-off nozzle at each floor landing. The length of the hose reel hose should be enough to reach the farthest corner of the floor. Hose-box with 15 meters long 63mm. dia. hose and 12.5 mm. bore nozzle at alternate floors. The Hose-reel hose should be capable of 45 liters per min.
Fire-service inlet should be installed at a point near the entry to the premises where a Fire service vehicle can approach easily.
A permanent hydrant point comprising of 63 mm dia size 2nos of hydrant valves should be installed at the terrace level.
Overhead tank Refilling bypass connection should be done at the terrace level.
The Overhead tank shall be of a capacity of not less than 20,000 liters. The Underground tank shall be of not less than 1,00,000 liters.

2. FIRE LIFT :

The Fire Lift and all the lifts should have a provision to ground automatically in case of electricity failure. Each building should have at least one lift as a Fire-Lift and if the building is divided into two or more parts then each should have a Fire-Lift. Lift-well should have blowers to pressurise the lift-well so connected that it will automatically operate when alarm call point is operate, so that it prevents the lift well getting smoke logged.

3. FIRE ALARM:

Fire alarm call point to be installed at each floor with sounders capable of being heard all throughout the building.

4. FIRE EXTINGUISHERS

One Carbon Dioxide (CO2) type extinguisher of 4.5 kg. with ISI mark, and one extinguisher of 9kg. Dry Chemical Powder (DCP) type extinguisher with ISI mark to be installed on each floor in case of commercial building.
One Carbon Dioxide (CO2) type extinguisher of 4.5 kg. with ISI mark, OR Two Carbon Dioxide (Co2) type extinguisher of 2 kg. with ISI mark capacity an alternate fronts in case of residential building.
If the building is divided into two or more parts then each part should have these extinguishers installed.

5. STAIRCASE :

The staircases has to be open from at least one or two sides but if the staircase is in the centre core of the buildings it has to be pressurized to prevent it from getting smoke logged. The Risers/Down-corner should be located in the staircase or close to it to make it easily approachable in case of Fire from the floor below or above.

6. BASEMENT :

The basement of 200 sq. meters or more should be protected with Automatic Sprinkler system with at least one sprinkler head for actual Car parking space.
Additionally be protected by a Hydrant outlet and two 25 mm. bore Hose-reel hoses with 6 mm. bore nozzles at each basement level.

7. LIGHTENING ARRESTER :

A lightening arrester should also be installed and be properly earthed to prevent damage to the building when the lightening strikes.

8. PHOTO LUMINESCENT (AUTO GLOW) SIGNAGES :

If the building fails in a confined area or if it has an enclosed staircase or is not well lit-up on the inside, then adequate photo luminescent (auto glow) signage's should be displayed at each floor / landing (staircase) clearly and along all exit routes leading to the ground level. The signage should indicate fire fighting, fire safety equipment present on the respective floor/landing/doorway/exit and along all exit routes leading to the ground level.

9. ELECTRIC POWER SUPPLY TO THE ENTIRE FIRE-SAFETY SYSTEM

Electricity supply to the fire pump, fire alarm system, staircase pressurization system and the lift should be made available from Main Electrical supply. (i.e. from Electrical power supply of the company) This is to ensure availability of power supply to the fire protection & Safety system even after the main electrical supply to the building is switched off at the time of fire.

10.INDIVIDUAL FIRE SEFTY SYSTEM

FIRE SEFTY SYSTEM SHOULD BE PROVIDED IN EVICIAL SHOW ROOM BY OWNER.

IMPORTANT INSTRUCTIONS:

After inspection of a low-rise building by the fire service authority,if the fire officer concerned feels th need for additional fire prevention/protection measures
/ ventilation system required or equipment (i.e. - Passive system / Suppression system
/ Fire door - Window / Detection system / Active system / Sprinkler / Drenchher etc.) as per Fire load / Fractio / Public gathering, Potential / Occupancy / Confined area,
those additional measures / equipment have to be implemented / installed.

SECTION — SHEET NO = 10/10

LAY OUT PLAN SHOWING PROP. COMM. BLDG. ON
F.P. NO.:236 T.P.S. NO :- 50 (BODAKDEV) (PRELIM.), R. SURVEY NO. 197/2/2
AT VILLAGE : BODAKDEV, TAL. :- DASKROI, DIST AHMEDABAD.

SCALE:1CM = 1.00 MTR.
ZONE: RESI.- II — USE: COMM

SCHEDULE FOR OPENING			STAIR DETAILS	
R.S. =	4.00 X 2.45	W = 2.00 X 2.45	WIDTH	- 2.00 MTR.
D. =	1.05 X 2.10		TREAD	- 0.30 MTR.
FPD1 =	0.75 X 2.10		RISER	- 0.15 MTR.
FPD2 =	0.75 X 2.10			
V. =	0.45 X 0.60			

COLOUR NOTE

PROP. WORK		PROP. DRAINAGE	TREE
PERCO. WELL		PLOT BOUND.	CONTAINER
ROAD		COMM. PLOT	
APP. WORK			

SUNIL RAMANBHAI PATEL — DASHARATHBHAI B.PATEL
SELF AND POA FOR — SELF AND POA FOR
KAMAL BHARATBHAI PATEL — SAMIR DASHARATHBHAI PATEL
RAJAL BHARATBHAI PATEL — SHEFALI SAMIRBHAI PATEL

DIVYANG DASHARATHBHAI PATEL
SELF AND POA FOR
BHARANTI DIVYANG PATEL

OWNER

SHILP DEVELOPERS	UMANG PATEL
AMC LIC NO. DEV/0804/2021	STELLI DESIGNER GRADE-1
FASH G. BRAHMBHATT	LIC. NO. [illegible]0050051782
304, SHILP-3, MANN PARTY PLOT	305, PARSHWANAM ELEGANT,
SINDHUBHAVAN ROAD,	SOLA, AHMEDABAD-60
BODKDEV, AHMEDABAD - 54.	
DEVLOPER	**STR. ENGINEER**

MAHESH NIJHONGA	RAJESH D. DAVE
305, HARVY COMPLEX,	204, SHILP-3, MANN PARTY PLOT
SUBHASH CHOWK,	CROSS ROAD, SINDHUBHAVAN ROAD,
MEMNAGAR, AHMEDABAD.	BODKDEV, AHMEDABAD - 54.
AMC - ER : 05040713219 R2	LIC No- CW 07742908/1
ENGINEER	**C.O.W.**

SCRUTINIZE COPY
DOC. No. 8105/13
TDO : SP, AMC

Ahmedabad Municipal Corporation
Case No. : BHATAN/WZ/2019110/GOR/A793/RSM/1 — Zone: New West
Plan Approved as per terms and condition mentioned in the Commencement Certificate
Raja Chitthi Number : 8909/2911116/A7931/RSM/1
Date : 23/12/2019
Sign :
Site Inspector [Civil/Center] — Asst. T.D.O./Asst. E.O. [Civil/ Center] — CHATANYA J. DY. T.D.O. New West — D.A. Shah Dy.MC New West

AUTHORITY