

FIRE HYDRANT LEGEND

SR.	SYMBOL	DISCRIPTION
1		FIRE HYDRANT PIPE MAIN
2		SLUICE VALVE
3		NON RETURN VALVE
4		COUPLE HAND HYDRANT VALVE
5		LANDING HYDRANT VALVE
6		HOSE BOX
7		FIRST AID HOSE REEL
8		AIR RELEASE VALVE
9		TWO WAY SIAMESE CONNECTION
10		RISE OR DROP

FIRE NOTES :-

(1) HYDRANT SYSTEM WITH PUMP AT THE UG TANK OF A CAPCITY OF 800 LITRES PER MINUTE WITH MINIMUM 3 BAR PRESSURE MEASURED AT TERRACE LEVEL WITH HYDRANT VALVE,HOSE REEL HOSE ON/OFF SWITCH AT ALL FLOOR LEVELS OR

(1) ULTRA HIGH PRESSURE FIRE FIGHTING SYSTEM WITH A PUMP OF 160 LITRES PER MINUTE @ 100 BAR PRESSURE WITH FOG GUNS AND HOSE REELS AND ON/OFF SWITCHES AT EACH FLOOR LEVEL

(2) THE LIFTS AND THE LIFT WELLS COMING FROM UPPER FLOORS SHALL END AT THE GROUND LEVEL ONLY, OR ALTERNATIVELY FOR LIFTS GOING DOWN TO BASEMENT OF THIS BUILDING SHALL BE COVERED WITH TWO HOURS FIRE RESISTANT SMOKE DOOR CONSTRUCTION FROM ALL SIDES AT THE BASEMENT LEVELS AND THEIR ENTRY AT THE BASEMENT LEVELS SHALL BE ADDITIONALLY PROTECTED BY SPRINKLERS

(3) FIRE ALARM SYSTEM WITH SMOKE DETECTION ALARM SYSTEM SHALL BE PROVIDED

(4) THE STAIRCASE SHALL BE OPEN PREFERRALY CROSS VENTILATED ABOVE THE PARAPET WALL IF THE STAIRCASE NEEDS TO BE COVERED IT CAN BE FIXED LOUVERS OR GRILLS

(5) AT ALL FLOORS CONNECTING THE STAIRCASE THERE SHALL BE 2 HOURS FIRE RESISTANT SELF CLOSING DOORS INSTALLED TO PREVENT FIRE OR SMOKE REACHING THE STAIRCASE

(6) WIDTH OF THE STAIRCASE SHALL BE MINIMUM 2 METRES INSIDE TO INSIDE

(7) WHOLE OF THE BUILDING ALL ENCLOSURES AT ALL FLOORS INCLUDING THE BASEMENT SHALL BE PROTECTED BY SPRINKLER SYSTEM (WITH 57 DEGREE CELSIUS SPRINKLER HEADS) ALONG WITH THE HYDRANT, HOSE REELS, EXTINGUISHERS,ETC

(8) BASEMENT SHALL HAVE NATURAL VENTILATION PROVIDED OR MECHANICAL VENTILATION WITH DUCTS TO HAVE 6 AIR CHANGES PER HOUR

USE & UNIT TABLE

FLOOR	UNIT / USE BLOCK :A	UNIT / USE BLOCK :B	UNIT / USE BLOCK :C+D	UNIT TOTAL
BASEMENT	PARKING	PARKING	STORE + PARKING	—
GR. FLOOR	32 COMM.	PARKING	PARKING	32
1st. FLOOR	31 COMM.	06 RESI.	08 RESI.	31+14 = 45
2nd. FLOOR	31 COMM.	06 RESI.	08 RESI.	31+14 = 45
3rd. FLOOR	12 COMM.	06 RESI.	08 RESI.	12+14 = 26
4th. FLOOR	12 COMM.	06 RESI.	08 RESI.	12+14 = 26
5th. FLOOR	—	08 RESI.	06 RESI.	14
6th. FLOOR	—	08 RESI.	06 RESI.	14
7th. FLOOR	—	08 RESI.	06 RESI.	14
TOTAL	118 COMM.	42 RESI.	56 RESI.	118+98 = 216

COMMUNITY BIN CALC. (COMM.)

TOTAL COMM FL AREA = 5691.36 SQ.MT.
CONTAINER REQD = 100.00 SQ.MT = 1 NOS. (20 LTRS CAP)
= 5691.36 FL. AREA = 56.91 SAY 57 NOS Container BIN REQ. (CAP. 20 LIT.)
MAXIMUM CAPACITY OF CONTAINER = 80 LTRS
15 NOS CONTAINER BIN PROVIDED FOR COMMERCIAL (CAP. 80.00 LIT.)

COMMUNITY BIN CALC (RESI.)

TOTAL NOS OF UNIT = 98 NOS
CONT. REQD = 1 UNIT = 1 NOS (10 LT CAP)
MAXIMUM CAPACITY OF CONT = 80 LTRS
80 LTRS = 8 UNIT = 1 CONT (80 LTRS CAP)
= 98 NOS UNITS / 8
= 12.25 CONTAINER REQUIRED
SAY = 13 NOS CONTAINER REQUIRED
13 NOS CONTAINER PROVIDED OF 80 LTRS CAP.

B.UP AREA TABLE — IN SQ.MT.

FLOOR	BLOCK A	BLOCK B	BLOCK C+D	TOTAL
BASEMENT	—	—	3907.07	3907.07
GR. FL. (H.P.)	—	524.07	541.45	1065.52
GR. FL. (S.P.)	1279.04	—	109.86	1388.90
1st. FLOOR	1279.04	498.21	651.31	2428.56
2nd. FLOOR	1279.04	498.21	651.31	2428.56
3rd. FLOOR	1279.04	498.21	651.31	2428.56
4th. FLOOR	1279.04	498.21	651.31	2428.56
5th. FLOOR	—	498.21	651.31	1149.52
6th. FLOOR	—	498.21	651.31	1149.52
7th. FLOOR	—	498.21	651.31	1149.52
STAIR CABIN	121.32	43.83	87.56	252.51
LMR & OHWT	86.99	27.60	57.41	172.00
TOTAL	6603.51	4082.77	9262.52	19948.80

F.S.I. & FLOOR AREA TABLE — IN SQ.MT.

FLOOR	BLOCK A	BLOCK B	BLOCK C+D	TOTAL
Basement (Store)	—	—	138.31	138.31
GR. FL. (S.P.)	1142.00	—	109.86	1251.86
1st. FLOOR	1137.34	432.60	566.06	2136.00
2nd. FLOOR	1137.34	432.60	566.06	2136.00
3rd. FLOOR	1137.34	432.60	566.06	2136.00
4th. FLOOR	1137.34	432.60	566.06	2136.00
5th. FLOOR	—	432.60	566.06	998.66
6th. FLOOR	—	432.60	566.06	998.66
7th. FLOOR	—	432.60	566.06	998.66
TOTAL	5691.36	3028.20	4210.59	12930.15

LAYOUT PLAN — SHEET NO. :- A1/6

LAYOUT PLAN SHOWING RESI.+COMM. BUILDING ON SUR. NO.: 1212, O.P. NO.: 52 F.P. NO.: 52, PRELIMINARY T.P.S. NO.: 84 (VATVA - IV), VILLAGE & TA.: VATVA, DISTRICT : AHMEDABAD.

SCALE - 1.00 CM. = 2.00 MT. — BLOCK :- A

ZONE - RESIDENCE - I — USE - RESI + COMM

AREA TABLE — IN SQ.MTS.

PLOT AREA OF F.P.NO. 52	5688.00
AREA GOING IN ROAD	212.60
NET PLOT AREA OF F.P.NO. 52	5675.40
REQ. COMMON PLOT AREA @ 10 % (5675.40 x0.10)	567.54
PROVI. COMMON PLOT AREA	570.37
PERMI. F.S.I. AREA (5688.00 x 1.8)	10598.40
PERMI. CHARGE F.S.I.AREA (5688.00 x 0.9)	5299.20
TOTAL PERMI + CHARG. F.S.I. AREA (5688.00 x 2.7)	15897.60
TOTAL USED F.S.I. AREA	12930.15
CHARG. F.S.I. ARE USED	2331.79

COLOUR NOTES : PLOT BOUNDRY, PROP. WORK, DRIVE WAY, ROAD, DRAINAGE, COMMON PLOT, PERCO WELL, TREE, COM. BIN

VIAAN BUILDCON
LIC. NO.: DEV789100821
DEVELOPER

VIAAN BUILDCON
Partner
OWNER

HILESH P. KHERNAR
C-2/102, Rushkar Residency, B/h. Annapurna Restaurant, Vastrapur, Ahmedabad.
AMC LIC. No. CW 04012110231
CLERK OF WORK

HILESH P. KHERNAR
C-2/102, RUSHKAR RESIDENCY, B/H. ANNAPURNA RESTAURANT, VASTRAPUR, AHMEDABAD.
ENGINEER

R. C. UPADHYAY
STRUCTURE ENGINEER

NOTES :-

- ENGINEER IS FULLY RESPONSIBLE FOR LEAVING OPEN SPACE AND MARGIN
- THE DEPTH AND POSITION OF EXISTING SEWERAGE MAIN HOLE IS VERIFIED BY ME ON SITE AND PREMISES CAN GET DRAINAGE CONNECTION
- IT IS CERTIFY THAT ACCORDING TO CGDCR 2017, ALL REQUIREMENTS OF THE BUILDING ARE CHECKED AND NECESSARY ACTION ARE TAKEN
- IT IS CERTIFY THAT ACCORDING TO THE CLAUSE NO 3.5.3 OF THE CGDCR 2017 THE STRUCTURE OF THE BUILDING IS DESIGN AS PER THE NORMS OF THE INDIAN STANDARDS
- DESIGN OF STAIRCASE AND RAILING IS PROVIDED AS PER THE PROVISION OF THE CLAUSE NO. 21.1.12 AND 21.1.14 AND 20.6 OF CGDCR 2017.
- PEDESTRIANS RAMP IS PROVIDED AS PER THE PROVISION OF THE CLAUSE NO. 21.1.5 OF CGDCR 2017
- LIFT IS PROVIDED AS PER THE PROVISION OF THE CLAUSE NO. 21.1.9 AND 20.9 OF CGDCR 2017
- WATER TANK IS PROVIDED AS PER THE PROVISION OF THE CLAUSE NO. 21.6 OF CGDCR 2017.
- SEPARATE LATRIN BLOCK IS PROVIDED AT GROUND LEVEL FOR EACH UNIT
- WATER TANK FOR FIRE SAFETY REQUIREMENT PROVIDED AS PER CHAPTER NO. 22.21 OF CGDCR 2017.
- ELECTRICAL INFRASTRUCTURE SHALL BE PROVIDED AS PER CLAUSE NO. 21.11 OF CGDCR 2017.
- DRINKING WATER FACILITY FOR DISABLED PERSONS IS PROVIDED AS PER THE CLAUSE NO. 21.5.7.9 CGDCR 2017.
- DRAINAGE FACILITY IS PROVIDED AS PER THE CLAUSE NO. 21.10 OF CGDCR 2017
- SLOPE OF THE PARKING PLACE IS TO BE PROVIDED AS PER THE CLAUSE NO. 21.7.2 OF CGDCR 2017
- ENTRANCE OF THE BUILDING IS PROVIDED AS PER THE CLAUSE NO. 21.1.7 OF CGDCR 2017
- THE PAVING OF BUILDING INTURNAL PLOT AS PER THE PROVI. OF THE CLAUSE NO. 21.1.4 OF CGDCR 2017
- THE STRUCTURE OF THE BUILDING IS OF SEISMIC AS PER THE NORMS OF THE SPECIFIED IN THE INDIAN STANDARD AND TAKE NECESSARY ACTION SHALL BE TAKEN FOR THE STRUCTURAL SAFETY DURING THE CONSTRUCTION
- RAIN WATER STORAGE TANK AND RAIN WATER HARVESTING SYSTEM IS PROVIDED AS PER THE CLAUSE NO. 25.2.7 OF CGDCR 2017
- COMMUNITY BIN PROVIDED AS PER THE PROVISION OF THE CLAUSE NO. 25.3 OF CGDCR 2017
- TREE PLANTATION IS PROVIDED AS PER THE CLAUSE NO. 25.5 OF CGDCR 2017
- MAINTENANCE AND UPGRADATION OF BUILDING IS AS PER CHAPTER NO. 22 OF CGDCR 2017
- FIRE SAFETY SYSTEM IS PROVIDED AS PER CHAPTER NO. 22 OF CGDCR 2017
- MARGINAL SPACE & CELLAR SLAB SHALL HAVE LOAD BEARING CAPACITY OF 40KN/SQ TONNES PER SQ.M/SQ METER SHALL BE PROVIDED AS PER CHAPTER NO. 22.3 OF CGDCR 2017

AUTHORITY

Scanned with CamScanner