AFFORDABLE HOUSING PROJECT

REVISED PLAN SHOWING RESIDENTIAL AFFORDABLE HOUSING
RESI. + COMM. BUILDING ON F.P. NO: 3 / 1, R.S. NO: 2/3,
PRELIMINARY T.P.S. NO: 46 (MOTER-AMIYAPUR-SUGHAD)
MOJE: MOTERA, TAL.: SABARMATI, DIST: AHMEDABAD.

SCALE – 1 : 100
ZONE : RESIDENCE–II
USE OF CONSTRUCTION : RESI.+COMM.(R.A.H.)

AREA TABLE :- IN SQ.MT.

	APP.	REV.
PLOT AREA OF F.P. NO:3 / 1	1396.00	1396.00
PROP. B.A. ON GR. FLOOR	566.84	566.84
PROP. B.A. ON GR. FLOOR(ELE.SUB ST.)	--	20.44
TOTAL PROP.B.A.(WITH ELE.SUB.ST.)	--	587.28
OPEN PLOT AREA	829.16	808.72

F.S.I AREA TABLE IN SQ.MT.

	APP.	REV.
PERMI. F.S.I. AREA 1: 1.2 (1396.00 X 1.2)	1675.20	1675.20
PERMI. CHAR. F.S.I. AREA @ 0.6 (1396.00X 0.6)	837.60	837.60
TOTAL PERMI. F.S.I. AREA @ 1.8 (1396.00X 1.8)	2512.80	2512.80
FSI AREA ON GR. FLOOR	172.55	172.38
FSI AREA ON 1ST FLOOR	474.12	480.93
FSI AREA ON 2ND FLOOR	474.12	480.93
FSI AREA ON 3RD FLOOR	474.12	480.93
FSI AREA ON 4TH FLOOR	474.12	480.93
FSI AREA ON 5TH FLOOR	442.56	413.69
TOTAL F.S.I AREA USED	2511.59	2509.79
CHARGEBLE FSI AREA USED (2509.79 - 1675.20)	836.39	834.59

TENEMENT & FLOOR AREA TABLE

	USE APP.	USE REV.	UNIT APP.	UNIT REV.	FLOOR AREA APP.	FLOOR AREA REV.
BASEMENT	PARK.	PARK.	-	-	-	-
GROUND	PARK. + COMM.	PARK. + COMM.	7 NOS.	7 NOS.	172.55	172.38
FIRST	RESI.	RESI.	8 NOS.	7 NOS.	474.12	480.93
SECOND	RESI.	RESI.	8 NOS.	7 NOS.	474.12	480.93
THIRD	RESI.	RESI.	8 NOS.	7 NOS.	474.12	480.93
FOURTH	RESI.	RESI.	8 NOS.	7 NOS.	474.12	480.93
FIFTH	RESI.	RESI.	8 NOS.	6 NOS.	442.56	413.69
TOTAL			7+40 NOS.	7+34 NOS.	2511.59	2509.79

BUILT UP AREA TABLE

FLOOR	APP.	REV.
BASEMENT	834.19	834.19
GROUND	566.84	587.28
FIRST	545.78	545.78
SECOND	545.78	545.78
THIRD	545.78	545.78
FOURTH	545.78	545.78
FIFTH	514.67	478.54
STAIR CABIN	80.85	80.85
L.M.R. & O.H.W.T.	59.09	59.09
TOTAL	4238.76	4223.07

BUILT UP AREA CALCULATION

GR. FLOOR
25.98X30.44 = 790.83
0.30X5.94 = 1.78 = 792.61

LESS
(1) 2.25X3.12 = 7.02
(2) 1.68X5.94 = 9.97
(3) 2.25X2.86 = 6.43
(4) 0.61X15.08 = 9.19
(5) 6.63X0.23 = 1.52
(6) 5.30X0.61 = 3.23
(7) 3.27X0.64 = 0.13
(8) 4.15X3.39 = 14.06
(9) 4.76X5.52 = 26.27
(10) 13.83X8.00 = 110.64
(11) 1.94X2.18 = 4.22
(12) 5.52X3.91 = 21.58
(13) 3.73X0.99 = 3.69
(14) 0.27X4.46 = 1.20
(15) 0.27X3.12 = 0.84
(16) 1.49X1.94X2 = 5.78 = 225.77

NET B.A. ON GR. FLOOR = 566.84 SQ.MT.

BUILT-UP AREA CALCULATION(H.P.)

NET BUILT–UP ON G.F. =566.84
NET F.S.I AREA ON G.F. =172.38
NET B.A. AREA ON G.F.(S.P) =
NET BUILT–UP ON H.P. =394.46 SQ.MT.

FSI AREA CALCULATION

GR. FLOOR
2X0.57X4.88 = 5.56
2X6.76X8.00 = 108.16
2X3.33X6.82 = 45.42
3.28X3.28 = 10.75
1.26X1.98 = 2.49 = 172.38

GENERAL NOTES

- ENGINEER IS FULLY RESPONSIBLE FOR LEAVING OPEN SPACE AND MARGIN.
- THE DEPTH AND POSITION OF EXISTING MUNICIPAL MANHOLE IS VERYFIED ME ON SITE AND PRMISES GATES DRAINAGE CONNECTION.
- IT IS CERTIFY THAT ACCORDING TO G.D.C.R. 2021 ALL REQUIREMENTS OF THE BUILDING ARE CHECKED AND NECESSARY ACTIONS ARE TAKEN.
- IT IS CERTIFY THAT ACCORDING TO THE CLAUSE NO: 4.5.3 OF THE G.D.C.R. 2021 THE STRUCTURE OF THE BUILDING IS DESIGN AS PER THE NORMES OF THE INDIAN STANDARDS.
- DESIGN OF STAIRCASE AND RAILING IS PROVIDED AS PER THE PROVOSION OF THE CLASE NO: 23.1.12 AND 23.14 AND 24.6 OF DRAFT GDR.
- PEDESTRIAS RAMP IS PROVIDED AS PER THE PROVISION OF THE CLASE NO: 23.1.5 OF G.D.C.R. 2021.
- LIFT IS PROVIDED AS PER THE PROVISION OF THE CLAUSE NO: 23.12 AND 24.7 OF G.D.C.R. 2021.
- WATER TANK IS PROVIDED AS PER THE PROVISION OF THE CLAUSE NO: 23.6 OF G.D.C.R. 2021.
- SEPARATE LETTER BOX IS PROVIDED AT GROUND LEVEL FOR EACH UNIT.
- WATER TANK FOR FIRE SAFETY REQUIREMENT PROVIDED AS PER THE CHEPTER NO: 24 OF G.D.C.R. 2021.
- ELECTRICAL INFRASTRUCTURE SHALL BE PROVIDED AS PER CLAUSE NO: 23.11.
- DRINKING WATER FACILITY FOR DISABLE PERSONS IS PROVIDED AS PER CLAUSE NO: 23.6.2 OF G.D.C.R. 2021.
- DRAINAGE FACILITY IS PROVIDED AS PER CLAUSE NO:23.10 OF THE G.D.C.R. 2021.
- SIGNAGES OF THE PARKING PLACE IS TO BE PROVIDED AS PER CLAUSE NO: 23.7 OF G.D.C.R. 2021.
- ENTRANCE OF THE BUILDING IS PROVIDED AS PER CLAUSE NO: 23.1.7 OF THE G.D.C.R. 2021.
- THE PAVING OF THE BUILDING UNIT/FINAL PLOT AS PER THE PROVISION OF THE CLAUSE NO: 23.1.4 OF G.D.C.R. 2021.
- THE STRUCTURE OF THE BUILDING IS AS PER THE NORMS OF THE SPESIFIED IN THE INDIAN STANDARD AND TAKE NECESSARY ACTION FOR THE STRUCTURAL SAFETY DURING THE CONSTRUCTION.
- RAIN WATER STORAGE TANK AND RAIN WATER HARVESTING SYSTEM IS PROVIDED AS PER THE CLAUSE NO: 27.2 OF G.D.C.R. 2021.
- COMMUNITY BIN PROVIDED AS PER THE PROVISION OF THE CLAUSE NO: 27.3 OF G.D.C.R. 2021.
- TREE PLANTATION IS PROVIDED AS PER THE CLAUSE NO: 27.5 OF G.D.C.R. 2021.
- FIRE SAFETY SYSTEM IS PROVIDED AS PER THE CHAPTER NO: 24 OF G.D.C.R. 2021.
- MAINTANANCE AND UPGRADATION OF BUILDING IS AS PER THE CHAPTER NO: 29 OF G.D.C.R. 2021

FIRE SAFEGUARD SYSTEM:

ON/OFF SWITCHES LOCATED NEAR THE HOSE REEL HOSE OR HYDRANT OUTLET AT EACH FLOOR FOR THE MAIN FIRE PUMP AT UNDERGROUND WATER TANK WITH A CAPACITY TO DISCHARGE 900 LITERS PER MINUTE AT 3 BAR PRESSURE AS MEASURED AT THE TERRACE LEVEL SHOULD BE INSTALLED.

THE RISER FOR THE BUILDINGS EXCEEDING 15 METERS HEIGHT SHOULD NOT BE OF LESS THAN 100 MM. INTERNAL DIAMETER. THE RISER SHOULD BE CONNECTED TO THE BOTTOM OF THE TERRACE TANK WITH A STOP VALVE AND A WAY TO ACT A DOWN-COMER.

ONE RISER IS REQUIRED FOR EVERY 1000 SQ. METERS FLOOR AREA AND IF THE BUILDING IS DIVIDED INTO, TWO OR MORE PARTS THEN EACH PART SHOULD HAVE A SEPARATE RISER WITH ALL THE FITTINGS AT EACH FLOOR LEVEL.

EACH FLOOR SHOULD HAVE ONE HYDRANT OUTLET WITH A COUPLING FOR ATTACHING A 63 MM. DIA. HOSE, 25 MM. BORE HOSE-REEL HOSE WITH 6 MM. SHOT- OFF NOZZLE AT EACH FLOOR LANDING. THE LENGTH OF THE HOSE SHOULD BE ENOUGH TO REACH THE FARTHEST CORNER OR THE FLOOR. HOSE-BOX WITH 15 METERS LONG 63 MM. DIA. HOSE AND 12.5 MM. BORE NOZZLE AT ALTERNATE FLOORS. THE HOSE-REEL HOSE SHOULD BE COUPLED TO THE RISER.

FIRE - SERVICE INLET SHOULD BE INSTALLED AT A POINT NEAR THE ENTRY TO THE PREMISES WHERE A FIRE SERVICE VEHICLE CAN APPROACH EASILY. A PERMANENT HYDRANT POINT COMPRISING OF 63 MM DIA SIZE 2 NOS OF HYDRANT VALVES SHOULD BE INSTALLED AT THE TERRACE LEVEL OVERHEAD TANK REFILLING BYPASS CONNECTION SHOULD BE DONE AT THE TERRACE LEVEL.

THE OVERHEAD TANK SHALL BE OF A CAPACITY OF NOT LESS THAN 20,000 LITERS. THE UNDERGROUND TANK SHALL BE OF NOT LESS THAN 1,00,000 LITERS.

(2) FIRE LIFT :

THE FIRE-LIFT AND ALL LIFTS SHOULD HAVE A PROVISION TO GROUND TO AUTOMATICALLY IN CASE OF ELECTRICITY FAILURE. EACH BUILDING SHOULD HAVE AT LEAST ONE LIFT AS A FIRE LIFT AND IF THE BUILDING IS DIVIDED INTO A MORE PARTS THEN EACH PART SHOULD HAVE A FIRE-LIFT. LIFT-WELL SHOULD HAVE BLOWERS TO PRESSURIZE THE LIFT -WELL SO CONNECTED THAT IT WILL AUTOMATICALLY OPERATE WHEN ALARM CALL POINT IS OPERATE, SO THAT IT PREVENTS THE LIFT WELL GETTING SMOKE LOGGED.

(3) FIRE ALARM :

FIRE ALARM CALL POINT TO BE INSTALLED AT EACH FLOOR WITH SOUNDERS CAPABLE OF BEING HEARD ALL THROUGHOUT THE BUILDING.

(4) FIRE EXTINGUISHER :

ONE CARBON DIOXIDE (CO2) TYPE EXTINGUISHER OF 4.5 KG. WITH ISI MARK, AND ONE EXTINGUISHER OF 5 KG. DRY CHEMICAL POWDER (DCP) TYPE EXTINGUISHER WITH ISI MARK TO INSTALLED ON EACH FLOOR IN CASE OF COMMERCIAL BUILDING.

ONE CARBON DIOXIDE (CO2) TYPE EXTINGUISHER OF 4.5 KG. WITH ISI MARK, OR TWO CARBON DIOXIDE (CO2) TYPE EXTINGUISHER OF 2 KG. CAPACITY ON EACH FLOOR AND 5 KG. DRY CHEMICAL POWDER (DCP) WITH ISI MARK TYPE EXTINGUISHER ON ALTERNATE FLOOR IN CASE OF RESIDENTIAL BUILDINGS.

IF THE BUILDING IS DIVIDED INTO TWO OR MORE PARTS THEN EACH PART SHOULD HAVE THESE EXTINGUISHERS INSTALLED.

(5) STAIRCASE :

THE STAIRCASE HAS TO BE OPEN FROM AT LEAST ONE OR TWO SIDES BUT IF THE STAIRCASE IS IN THE CENTRE CORE OF THE BUILDING IT HAS TO BE PRESSURIZED TO PREVENT IT FROM GETTING SMOKE LOGGED.

THE RISER / DOWN - COMER SHOULD BE LOCATED IN THE STAIRCASE OR CLOSE TO IT IN TO MAKE IT EASILY APPROACHABLE IN CASE OF FIRE FROM THE FLOOR BELOW OR ABOVE.

(6) BASEMENT :

THE BASEMENT OF 200 SQ. METERS OR MORE SHOULD BE PROTECTED WITH AUTOMATIC SPRINKLER SYSTEM WITH AT LEAST ONE SPRINKLE HEAD FOR ACTUAL CAR PARKING SPACE.

ADDITIONALLY BE PROTECTED BY A HYDRANT OUTLET AND TWO 25 MM.BORE HOSE-REEL HOSES WITH 6MM. BORE NOZZLES AT EACH BASEMENT LEVEL.

(7) LIGHTNING ARRESTER :

A LIGHTNING ARRESTER SHOULD ALSO BE INSTALLED AND BE PROPERLY EARTHED TO PREVENT DAMAGE TO THE BUILDING WHEN THE LIGHTENING STRIKES.

(8) EXITS LUMINESCENT / AUTO GLOW) SIGNAGES :

IF THE BUILDING FALLS IN A CONFINED AREA OR IF IT HAS AN ENCLOSED STAIRCASE OR IS NOT WELL LIT-UP ON THE INSIDE, THEN ADEQUATE PHOTO LUMINESCENT (AUTO GLOW) SIGNAGES SHOULD BE DISPLAYED AT EACH FLOOR / LANDING / PATHWAY / GROUND AND ALONG ALL EXIT ROUTES LEADING TO THE GROUND LEVEL. THE SIGNAGE SHOULD INDICATE FIRE FIGHTING, FIRE SAFETY, FIRST-AID AND OTHER SAFETY EQUIPMENT PRESENT ON THE RESPECTIVE FLOOR / LANDING / PATHWAY / DGO - END AND ALONG ALL EXIT ROUTES LEADING TO THE GROUND LEVEL.

(9) ELECTRIC POWER SUPPLY TO THE ENTIRE FIRE - SAFETY SYSTEM :

ELECTRICITY SUPPLY TO THE FIRE PUMP, FIRE ALARM SYSTEM, STAIRCASE PRESSURIZATION SYSTEM AND FIRE LIFT SHOULD BE MADE AVAILABLE FROM THE MAIN ELECTRICAL SUPPLY, I.E. FROM ELECTRICAL POWER SUPPLY OF THE COMPANY ; THIS IS TO ENSURE AVAILABILITY OF POWER SUPPLY TO THE FIRE PROTECTION & SAFETY SYSTEM EVEN AFTER THE MAIN ELECTRICAL SUPPLY TO THE BUILDING IS SWITCHED OFF THE TIME OF FIRE.

(10) IMPORTANT INSTRUCTIONS :

AFTER INSPECTION OF A LOW-RISE BUILDING BY THE FIRE SERVICES AUTHORITY , IF THE FIRE OFFICER CONCERNED FEELS THE NEED FOR ADDITIONAL FIRE PREVENTION / PROTECTION / VENTILATION SYSTEM REQUIRED OR EQUIPMENT (I.E. PASSIVE SYSTEM / SPRINKLER / DRENCHER ETC.) AS PER FIRE LOAD / FIRE RISK / PUBLIC GETHERING, POTENTIAL / OCCUPANCY / CONFINED AREA, THOSE ADDITIONAL MEASURES / EQUIPEMENT HAVE TO BE IMPLEMENTED / INSTALLED.

(11) LENGED

1 FIRE HYDRANT SYSTEM PIPE MAIN
2 SINGEL HEADED HYDRANT VALVE
3 SLUICE VALVE
4 TWOWAY SIAMES CONNECTION
5 RISE OR DROP
6 NON RETURN VALVE
7 REDUCER
8 FIRE HOUSE BOX
9 HOSE REEL HOSE
10 D.C.P. &CO.2
11 HYDRAUNT VALVE

R.C.C COL. FOOTING SECTION

STR DETAIL AS PER DESIGN BY STR ENGINEER

UNIT AREA TABLE

FLOOR	UNIT NO	U.B.A. BLOCK–A	U.B.A. BLOCK–B
GROUND	1	27.32	--
	2	26.71	--
	3	22.92	--
	4	13.71	--
	5	22.80	--
	6	26.71	--
	7	27.32	--
FIRST TO FOURTH	101,201,301,401	65.13	71.06
	102,202,302,402	65.59	71.62
	103,203,303,403	65.36	75.62
	104,204,304,404	64.90	--
FIFTH	501	63.19	72.08
	502	65.59	79.92
	503	65.36	--
	504	62.99	--

SANITORY PROVISION (FOR COMM.)

GR. FLOOR
FLOOR AREA =172.38 SQ.MT.
172.38/4=43.09 SAY 44 USERS

REQD. SANITARY FACILITY	URINAL	WC MALE	WC FEMALE	PHY. HENDI. TOILET
	2 NOS.	2 NOS.	2 NOS.	1 NOS.
	PROV. 5 TOILET IN SHOP			

PROV. GENERAL SANITARY FACILITY	URINAL	WC MALE	WC FEMALE	PHY. HENDI. TOILET
25%	1 NOS.	1 NOS.	1 NOS.	1 NOS.
	1,75X1.00 WC FOR DISSABLE PERSON.			

PARCOLATING WELL REQD.=1396.00/4000=0.34 SAY 1 NOS.
PARCOLATING WELL PROVIDED=1 NOS.

TREE PLANTATION REQD.=1.396.00X3/200=20.94 SAY 21 NOS.
TREE PLANTATION PROVIDED=21 NOS.

COMMUNITY BIN CALCULATION
FOR RESI.
COMUNITY BIN REQUIRED 10 LT. CAPACITY PER 1 UNIT
TOTAL 35 UNIT=35 NOS.X10 LT=350 LT. CAPACITY COMMUNITY BIN REQD.
COMUNITY BIN PROVIDED 80 LT. X 5 NOS.=400 LT. CAPACITY.
FOR NON RESI. USE :–
FLOOR AREA (TOTAL) :– 172.38 SQ. MTS.
100 SQ. MTS FL. AREA / 20 LTS.
172.38/5 = 34.47 SAY 34 LTS.
PROVI. 80 LTS. (80 X 1)=80 LT. COMM. BIN

FOR AFFORDABLE HOUSING UNIT AREA CALCULATION
MINIMUM UNIT = 31.41 SAY 32 UNITS
MAXIMUM UNIT = 83.76 SAY 84 UNITS
PROPOSED TOTAL UNIT = 34 UNITS

PERCOLATION WELL

FOR BUILDING UNIT 1500.00 SQ. MT. OR MORE AND UP TO 4000.00 SQ. MT. AND PART THERE OF IT.

KEY PLAN

SCALE:– 1CM.=40.0MT.

UNIT CATEGARY TABLE IN SQ.MT.

COMM. UNIT	COMM. F.S.I.	0 & UP TO 50.0 SQ.MT. UNIT	0 & UP TO 50.0 SQ.MT. F.S.I.	MORE THEN 50.0 & UP TO 66.0 SQ.MT. UNIT	MORE THEN 50.0 & UP TO 66.0 SQ.MT. F.S.I.	MORE THEN 66.0 SQ.MT. UNIT	MORE THEN 66.0 SQ.MT. F.S.I.
7 NOS.	172.38	--	--	20 NOS.	1301.05	14 NOS.	1036.36

CHARGEABLE F.S.I.AREA CALCULATION TABLE

	SQ.MT.
COMMERCIAL	4.85
MORE THAN 50.0 & UP TO 66.0 SQ.MT.	462.10
MORE THAN 66.0 & UP TO 80.0 SQ.MT.	367.64
TOTAL	834.59

DRAINAGE SECTION

UNIT B.A. CALCULATION (GR. FLOOR)

GR. FLOOR PLAN

15.00M WIDE T.P.S. ROAD

FRONT ELEVATION

SECTION A-A

GROUND FLOOR PLAN

BUILT UP AREA CALC:–
GROUND FLOOR
6.33 X 3.23 = 20.44 SMT

NOTES:
** AREA OF ELE. SUB STATION SHALL NOT CONSIDERED TOWARDS COMPUTATION OF PERMISSIBLE F.S.I. AS PER CL. NO: 13.4.3.12 & 13.6.10.9. GDCR - 2021.

SCHEDULE OF OPENING

DOOR
D =1.00X2.10
D1=0.90X2.10
D2=0.75X2.10
SD=2.75X2.10

WINDOWS
W =1.80X1.20 (WITH SAFETY GRILL)
W1=1.40X1.20 VENT
W2=0.90X1.20 V=0.60X0.60

RCC STAIR DETAIL

WIDTH=1.52M
TREAD=0.25M
RISER=0.15M

COLOUR NOTE

- PLOT BOUNDARY
- ROAD
- PROPOSED WORK
- PROPOSED DRAINAGE
- PERCOLATING WELL
- TREE
- APPROVED WORK
- APPROVED DRAINAGE
- SPRINKLER
- WORK APPROVED BUT NOT TO BE DONE

HARESH H. SHAH
220, ASHWAMEGH ELEGANCE, B/H. KALYAN JWELLERS, BHUDARPURA ROAD, AMBAWADI, AHMEDABAD-15.
ENG. LIC NO. 0023060721-R3
COW LIC NO. 0119250921-R3
ENGINEER.

HARESH H. SHAH
220, ASHWAMEGH ELEGANCE, B/H. KALYAN JWELLERS, BHUDARPURA ROAD, AMBAWADI, AHMEDABAD-15.
ENG. LIC NO. 0023060721-R3
COW LIC NO. 0119250921-R3
CLERK OF WORKS

ACHAL J. PARIKH
606, Sun Square, Nr. Nest Hotel, Navrangpura, Ahmedabad-9
AMC LIC.No. SD 0003250621R3
STRU.ENGINEER.

FOR, ANAND BUILDCON
PARTNER
OWNER

NIRMALKALA DEVELOPERS
AMIT M. OZA & PARTNERS
DEV. LIC.NO. 057190120
DEVELOPER

RESPONSIBILITY 45.G.C.R.-2021 4.5.4 & 4.6.1 :–
APPROVAL OF DRAWINGS AND ACCEPTANCE OF ANY STATEMENT, APPROVAL OF DRAWINGS AND, STRUCTURAL DRAWINGS, PROGRESS DOCUMENTS, STRUCTURAL REPORT, STRUCTURAL DRAWINGS, PROGRESS DOCUMENTS, COMPLETION CERTIFICATES SHALL NOT CERTIFICATE OR BUILDING COMPLETION CERTIFICATES SHALL NOT DISCHARGE THE OWNER, ENGINEER, ARCHITECT, CLERK OF WORKS, SITE SUPERVISOR, STRUCTURAL DESIGNER, DEVELOPER, OWNER FROM THEIR RESPONSIBILITIES, IMPLIED UNDER THE ACT, THE DEVELOPMENT CONTROL REGULATIONS AND THE LAWS OF TORT AND LOCAL ACTS.
LIMITATION OF LIABILITY :–
NOTWITHSTANDING ANY DEVELOPMENT PERMISSION GRANTED UNDER THE ACT AND THESE REGULATIONS, ANY PERSON UNDERTAKING ANY DEVELOPMENT WORK SHALL CONTINUE TO BE WHOLLY AND SOLELY LIABLE FOR ANY INJURY OR DAMAGE OR LOSS WHATSOEVER THAT MAY BE CAUSED TO ANY ONE IN OR AROUND THE AREA DURING SUCH CONSTRUCTION AND NO LIABILITY WHATSOEVER IN THIS REGARD SHALL BE CAST ON THE AUTHORITY

Ahmedabad Municipal Corporation
Case No. : BLNTSWZ/12011/GDDU/A5665/R1/M1 Zone: WEST
Plan Approved as per terms and condition mentioned in the Commencement Certificate
Raja Chitthi Number : 9122/12116/A5665/R1/M1
Date : 23/01/2018

Dy.T.D.O. (Civic Center) | Asst. T.D.O.Asst. E.O. (Civic Center) | Nilesh Baranda Dy T.D.O. WEST | ARJAV J. SHAH(IAS) Dy MC WEST

AUTHORITY.

SCRUTINIZE COPY NO. 1237 DT. 16/05/2018 TDO, BPSP, AMC