











PARKING AREA CALCULATION		
<u>PARKING REQ.</u>		Sq. Mt.
Total F.S.I. Bui. area 1273.27 @ 20% = 254.65		
Total Parking Req.	254.65	Sq. Mt.
<u>Parking Providing</u>		
1 X 16.59 X 18.68	= 309.90	
<u>LESS</u>		
1 X 4.76 X 4.98	= 23.70	} 27.35
1 X 1.60 X 2.28	= 3.65	
<u>TOTAL</u>	= 282.55	
Parking Req.	Parking Provi.	
254.65 Sq. Mt. <	282.55 Sq. Mt.	



<u>-BUILT UP AREA CALCULATION:-</u>	<u>-F.S.I. BUILT UP AREA CALCULATION:-</u>
<u>G.F. to 6th.F. BUILT UP AREA CAL.</u>	<u>F.F. TO 6th.F. F.S.I. BUILT UP AREA CAL.</u>
1 X 11.05 X 18.68 = 206.41	B.A.ON F.F. TO 6th. = 206.41 - STAIR & LIFT LESS
TOTAL = 206.41 X 7 = 1444.87	1 X 4.52 X 4.53 = 20.48 1 X 1.60 X 1.82 = 2.91 } = 23.39
<u>7th.FLOOR BUILT UP AREA CAL.</u>	TOTAL = 183.02 X 6 = 1098.12
B.A. ON G.F. = 206.41 LESS 2 X 1.32 X 1.13 = 2.98 2 X 1.07 X 2.00 = 4.28] -7.26 TOTAL = 199.15	<u>7th.F. F.S.I. BUILT UP AREA CAL.</u>
<u>STAIR ROOM BUILT UP AREA CAL.</u>	B.A.ON 7th. = 199.15 - STAIR & LIFT LESS
1 X 4.76 X 4.98 = 23.70 1 X 1.60 X 2.28 = 3.65 TOTAL = 27.35	1 X 4.52 X 4.53 = 20.48 1 X 1.60 X 1.82 = 2.91 2 X 1.32 X 0.23 = 0.61 } = 24.00 TOTAL = 175.15
<u>TOTAL BUILTUP AREA</u>	<u>TOTAL F.S.I. BUILT UP AREA CAL.</u>
1444.87 + 199.15 + 27.35 = 1671.37	TOTAL F.S.I. 1098.12 + 175.15 = 1273.27 472.285 = 2.695 < 2.70
	TOTAL PLOT AREA 472.285 SQ.MT. F.S.I. 472.285 X 1.70 1275.17 SQ.MT. F.S.I. 472.285 X 2.80 850.11 SQ.MT.



NAME OF WORK			
REV. RESL. HIGH RISE BUILDING PLAN		(DWE. - 3)	
AKSHAR DEVELOPERS PARTNERS			
OWNER'S NAME			
(1)SHRI HASMUKHBHAI SANATKUMAR PATEL (2)SHRI VIDYABHAI RAMTIBHAI VAGADIYA (3)SHRI HEMATIBHAI VASHIRAMBHAI BORCHIA (4)SHRI HARIKRUSHANABHAI SHAMTIBHAI CHAUHAN			
USE OF BLDG. : RESIDENCE (HIGH RISE)			
LOCATION : DHOLARIYA NAGAR (GAYATRINAGAR MAIN ROAD)			
VILLAGE : RAJKOT			
CITY :	RAJKOT	T.P.S. NO. :	5 (RAJKOT)
PLOT NO. :	74/75P	O.P. NO. :	49
SR. NO. :	336	F.P. NO. :	181/P
C. SR. NO. :	1739/P	WARD NO. :	14
C. SR. W. NO. :	8/1	SHEET NO. :	258

AREA TABLE		SQ. MT.
TOTAL PLOT AREA (PLOT NO. 75/F)		40.92
TOTAL PLOT AREA (PLOT NO. 74)		431.365
TOTAL PLOT AREA		472.285

FLOOR	PROP. BUILDUP	LESS IN P.S.I.	P. S. I USED	OPEN AREA	CARPET AREA
G. F.	206.41	206.41	—	265.875	—
P. F.	206.41	23.39	183.02	265.875	160.46
S. F.	206.41	23.39	183.02	265.875	160.46
T. F.	206.41	23.39	183.02	265.875	160.46
4th. F.	206.41	23.39	183.02	265.875	160.46
5th. F.	206.41	23.39	183.02	265.875	160.46
6th. F.	206.41	23.39	183.02	265.875	164.11
7th. F.	199.15	24.00	175.15	273.135	156.86
STAIR ROOM	27.35	27.35	—	—	—
TOTAL	1671.37	398.10	1273.27	—	1123.27

F. S. I. USED $\frac{1273.27}{472.285}$ $2.695 < 2.70$ PAID F.S.I. = 423.16 SQ.MT.

SCHEDULE		LEGEND
M.D. : 1.07X2.00	W : 2.00X1.20	PLOT BOUNDARY : _____
D : 0.90X1.00	W1 : 1.80X1.20	PROPOSED WORK : _____
D1 : 0.75X2.00	W2 : 1.20X1.20	DRAINAGE LINE : - - - -
V : 0.60X0.45	W3 : 1.13X1.20	
	W3 : 0.60X0.50	

OWNER **AKSHAR DEVELOPERS PARTNERS**
AND SIGNATURE AUTHORITY

X. हस्मुख भागलकुमार पटेल
SHRI HASMUKHBHAI SANATKUMAR PATEL

X.....
SHRI HARIKRUSHANABHAI SHAMJIBHAI CHAUHAN

ENGINEER	STRUCTURAL ENG.
----------	-----------------

RACHANA PLANNING
C.M.SRINGALA
201, OM COMPLEX, BHAKTINAGAR
ST. CIRCLE, TAOROB ROAD, RAJKOT
R.M.C. LIC. NO. - B149

AUTHORITY



The Boundaries of Plot

 shown on this Plan are subject
 to change and alteration by the
 Town Planning Officer T.P.
 Scheme, Rajkot.

तभीमे करेल विद्यास परवानगीही अरळ
अवघे अरळ कोर्म न.-उ थी लललल
परवानेदार आपेल प्रमल्लन मुजल
तमारी मासिगिनी जगपाना उद माप /
यतुसीमा जलवनी मांघडाम करानुं
रहेले. तेमां मुक धने संपुर्ण जगपाना
नमारी रहेले.

અન્યની સુવર્ણ :-
તા. ૨૯/૫/૨૦૦૧ ના રજાકરકીલકામનુ
નં. ૭ મુકામ દરેક એકેક રીપોર્ટ ના સુવર્ણ
સ્થાનને વાંચકામ દરમ્યાન વચારકામ લેવામાં
આવેલ બાંધકામ પરીક્ષણ જેવા કે કિનેટ, ડીક
તથા કિનેટ કોનક્રીટનું માન્ય લેખોરેટરી કારાર
પરીક્ષણ કરાવવું અને પરીક્ષણ ના રીપોર્ટ સ્થાપના
કારકીકેટ અરક જેવા કરકામતણે સામેલ
કારકીકેટ રહેશે.

કે.સ.નં. ૪૭૭	૨.શી.નં. ૪૪૪
તા. ૨૪/૭/૨૦	તા. ૩/૮/૨૦

OWNER'S COPY

APPROVED

Asst. Town Planner
Barnet Municipal Corporation